

Exhibit "B"

**Table 2
Riverland/Kennedy DRI Road Improvements**

Road	From	To	Residential Units	*Trip Threshold	Required Improvement	Status
Phase 1						
Community Blvd.	Discovery Way	E/W 3	700	828	2L	Portion Under Construction (Discovery Way to E/W 2)
Community Blvd.	E/W 3	Paar Dr.	2,000	2,023	2L	
Community Blvd.	Paar Dr.	Becker Rd.	2,500	3,219	2L	
E/W 3	Community Blvd.	N/S B	2,500	3,219	2L	
Phase 2						
Becker Rd.	Community Blvd.	N/S B	4,475	5,148	Widen to 4LD	
N/S B	Discovery Way	E/W 3	5,660	6,305	2L	Portion Under Construction (Discovery Way to 2,500 LF +/- South)
Paar Dr.	Community Blvd.	N/S B	5,660	6,305	2L	
Discovery Way	Community Blvd.	N/S B	4,080	4,762	2L	Under Construction
Discovery Way	N/S B	N/S A	5,660	6,305	2L	
Discovery Way	N/S A	Rangeline Rd.	5,660	6,305	2L	
N/S A	Discovery Way	E/W 3	5,660	6,305	2L	
Phase 3						
Community Blvd.	Discovery Way	E/W 3	10,661	11,440	Widen to 4LD	
Community Blvd.	E/W 3	Paar Dr.	10,661	11,440	Widen to 4LD	
Becker Rd.	Community Blvd.	N/S B	10,661	11,440	Widen to 4 6LD	

N/S B	Paar Dr.	Becker Rd.	10,661	11,440	Widen to 4LD	
Discovery Way	Community Blvd.	N/S B	10,661	11,440	Widen to 4LD	
Paar Dr.	Community Blvd.	N/S B	10,661	11,440	Widen to 4LD	
Phase 4						
N/S A	Discovery Way	E/W 3	11,700	13,461	Widen to 4LD	
N/S B	E/W 3	Paar Dr.	11,700	13,461	Widen to 4LD	
N/S B	Discovery Way	E/W 3	11,700	13,461	Widen to 4LD	
E/W 3	Community Blvd.	N/S B	11,700	13,461	Widen to 4LD	
E/W 3	N/S B	N/S A	11,700	13,461	Widen to 4LD	

*Riverland/Kennedy Cumulative Total Net External DRI p.m. Peak Hour Trips
L=Lane; D=Divided