



PERIMETER PLANTING (SEC. 154.03 C)
10' LANDSCAPE BUFFER

REQUIRED: 1 TREE / 30 LF.
1 SHRUB / 2 LF.
243 LF. - 42 LF. (INGRESS / EGRESS) = 201 LF.
201 / 30 = 7 TREES
201 / 2 = 101 SHRUBS

PROVIDED: 7 TREES (3 TYPE 'A' TREES, 2 TYPE 'B' PALMS, 6 NEW TYPE 'B' TREES)
114 SHRUBS

PERIMETER PLANTING (SEC. 154.03 C)
10' LANDSCAPE BUFFER

REQUIRED: 1 TREE / 30 LF.
1 SHRUB / 2 LF.
152 LF. (UNOBSTRUCTED)
152 / 30 = 5 TREES
152 / 2 = 76 SHRUBS

PROVIDED: 5 TREES (2 RELOCATED TYPE 'B' PALMS, 4 NEW TYPE 'A' TREES)
77 SHRUBS

PERIMETER PLANTING (SEC. 154.03 C)
10' LANDSCAPE BUFFER

REQUIRED: 1 TREE / 30 LF.
1 SHRUB / 2 LF.
199 LF. (UNOBSTRUCTED)
199 / 30 = 7 TREES
199 / 2 = 100 SHRUBS

PROVIDED: 7 TREES (4 TYPE 'B' PALMS, 10 NEW TYPE 'B' TREES)
106 SHRUBS

PERIMETER PLANTING (SEC. 154.03 C)
15' LANDSCAPE BUFFER (PORT ST. LUCIE BLVD. ONLY)

REQUIRED: 1 TREE / 30 LF.
1 SHRUB / 2 LF.
176 LF. - 25 LF. (INGRESS / EGRESS) = 151 LF.
151 / 30 = 5 TREES
151 / 2 = 76 SHRUBS

PROVIDED: 5 TREES (2 TYPE 'B' PALMS, 8 NEW TYPE 'B' TREES)
85 SHRUBS

Symb.	Quant.	Botanical Name	Common Name	Description	Native
Trees					
BSI	3	<i>Bursera simaruba</i>	Gumbo Limbo	12' O.A. HT. 2.5" CAL	Yes
CEN	1	<i>Conocarpus erectus</i>	Green Buttonwood	12' O.A. HT. 2.5" CAL	Yes
CES	10	<i>Conocarpus erectus</i> var. <i>sericeus</i>	Silver Buttonwood	12' O.A. HT. 2.5" CAL Multi-Trunk	Yes
LIN	14	<i>Lagerstroemia indica</i> sp.	Crape Myrtle	12' O.A. HT. 2.5" CAL Multi-Trunk	No
MVI	2	<i>Magnolia virginiana</i>	Sweet Bay Magnolia	12' O.A. HT. 2.5" CAL	Yes
QVI	5	<i>Quercus virginiana</i>	Live Oak	12' O.A. HT. 2.5" CAL	Yes
Palms					
SPA	10	<i>Sabal palmetto</i>	Sabal Palm	Relocated from on-site	Yes
TRA	6	<i>Thrinax radiata</i>	Florida Thatch Palm	Staggered, 6' CT. to 10' ct.	Yes
Understory Shrubs					
CH	191	<i>Chrysobalanus icaco</i> "Horizontal"	Horizontal Cocoplum	7G. Bush Full 24" min. HT.	Yes
CI	186	<i>Chrysobalanus icaco</i> "Red Tip"	Red Tip Cocoplum	7G. Bush Full 24" min. HT.	Yes
GG	70	<i>Galphimia galouca</i>	Thryallis	7G. Bush Full 24" min. HT.	No
MF	18	<i>Myrciathos fragrans</i>	Simpson Stopper	7G. Bush Full 24" min. HT.	Yes
SR	6	<i>Serenoa repens</i>	Saw Palmetto	3' x 3'	Yes
Grasses					
SS	3,443	<i>Stenotaphrum secundatum</i>	St. Augustine Grass	S.F. Area.	No
Groundcovers					
TBD	(+/- 8,267 sq. ft. area)				
Miscellaneous Groundcovers					
GR / RR	TBD	Gravel & River Rock Blend	Same	S.F. Area. 3" deep. Blend: 70% Gravel, 30% River Rock (Mixed Sizes)	
GR	TBD	Gravel	Same	S.F. Area. 2" deep.	
MU	TBD	Australian Pine Mulch	Same	No Cypress, Colored nor Synthetic Mulch	

