



City of Port St. Lucie
Procurement Management Division

121 SW Port St. Lucie Blvd., Port St. Lucie, FL 34984

EVALUATION TABULATION

IFB No. 20260079

Glades Wastewater Treatment Facility Deep Injection Well No. 2

RESPONSE DEADLINE: January 12, 2026 at 3:00 pm

Report Generated: Tuesday, January 13, 2026

SELECTED VENDOR TOTALS

Vendor	Total
Youngquist Brothers, LLC	\$0.00

GLADES WWTF INJECTION WELL IW-2 PROJECT NO. 63-0007

Cost Table

Glades WWTF Injection Well IW-2 Project No. 63-0007					Youngquist Brothers, LLC	
Selected	Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
Base Bid Item No.1 - Construction of Injection Well IW-2						
	1	General Conditions, Mobilization, and Demobilization	1	LS	\$6,390,000.00	\$6,390,000.00
	2	Drill pilot hole from 665 feet to 3,500 feet	2835	FT	\$500.00	\$1,417,500.00
	3	Provide and install drillable bridge plug at 2,600 feet	1	LS	\$25,000.00	\$25,000.00
Boreholes and Reamed Holes						
	4	64-inch diameter - pad level to approximately 195 feet	195	FT	\$650.00	\$126,750.00
	5	58-inch - diameter - approximately 195 feet to 665 feet	470	FT	\$650.00	\$305,500.00
	6	48-inch diameter - approximately 665 feet to 1,605 feet	940	FT	\$650.00	\$611,000.00

EVALUATION TABULATION

IFB No. 20260079

Glades Wastewater Treatment Facility Deep Injection Well No. 2

Glades WWTF Injection Well IW-2 Project No. 63-0007					Youngquist Brothers, LLC	
Selected	Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
	7	40-inch diameter - approximately 1,605 feet to 2,605 feet	1000	FT	\$650.00	\$650,000.00
	8	30-inch diameter - approximately 2,605 feet to 3,500 feet	895	FT	\$300.00	\$268,500.00
Casing						
	9	Furnish and install 58-inch carbon steel casing	190	FT	\$950.00	\$180,500.00
	10	Furnish and install 48-inch carbon steel casing	660	FT	\$750.00	\$495,000.00
	11	Furnish and install 40-inch carbon steel casing	1600	FT	\$600.00	\$960,000.00
	12	Furnish and install 30-inch carbon steel casing	2600	FT	\$650.00	\$1,690,000.00
Furnish and Emplace Cement and Additives						
	13	Cement 58-inch casing; includes cement-top temperature logs	190	LF	\$150.00	\$28,500.00
	14	Cement 48-inch casing; includes cement-top temperature logs	660	LF	\$150.00	\$99,000.00
	15	Backplug pilot hole with cement - approximately 810 feet to 1,700 feet	890	LF	\$150.00	\$133,500.00
	16	Cement 40-inch casing; includes cement-top temperature logs	1600	LF	\$200.00	\$320,000.00
	17	Backplug pilot hole with cement - approximately 1,750 feet to 2,600 feet	850	LF	\$150.00	\$127,500.00
	18	Cement 30-inch casing; includes cement-top temperature logs	2600	LF	\$200.00	\$520,000.00
Geophysical Logging:						

EVALUATION TABULATION

Invitation For Bid (IFB) - Glades Wastewater Treatment Facility Deep Injection Well No. 2

EVALUATION TABULATION

IFB No. 20260079

Glades Wastewater Treatment Facility Deep Injection Well No. 2

Glades WWTF Injection Well IW-2 Project No. 63-0007					Youngquist Brothers, LLC	
Selected	Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
	19	Perform borehole logging from 0 to 195 feet	1	LS	\$65,000.00	\$65,000.00
	20	Perform borehole logging from 190 to 665 feet	1	LS	\$65,000.00	\$65,000.00
	21	Perform pilot hole logging from 660 to 1,700 feet; static and dynamic	1	LS	\$85,000.00	\$85,000.00
	22	Perform reamed hole logging from 660 to 1,605 feet	1	LS	\$65,000.00	\$65,000.00
	23	Perform pilot hole logging from 1,600 to 3,500 feet; static and dynamic	1	LS	\$85,000.00	\$85,000.00
	24	Perform reamed hole logging from 1,600 to 2,605 feet	1	LS	\$65,000.00	\$65,000.00
	25	Perform reamed hole logging from 2,600 to 3,500 feet	1	LS	\$65,000.00	\$65,000.00
	26	Perform cement-bond, downhole video, background gamma-ray, and RTS logging	1	LS	\$195,000.00	\$195,000.00
	27	Collect and analyze 10-foot cores	8	EA	\$30,000.00	\$240,000.00
	28	Set up and perform inflatable packer testing	11	EA	\$40,000.00	\$440,000.00
	29	Set up and perform pressure test on 30-inch casing	1	LS	\$95,000.00	\$95,000.00
	30	Develop and collect final water quality sample in IW-2	1	LS	\$35,000.00	\$35,000.00
	31	Perform laboratory water quality analyses	1	LS	\$45,000.00	\$45,000.00
	32	Setup and Perform Injection Test of IW-2	1	LS	\$150,000.00	\$150,000.00

EVALUATION TABULATION

Invitation For Bid (IFB) - Glades Wastewater Treatment Facility Deep Injection Well No. 2

EVALUATION TABULATION

IFB No. 20260079

Glades Wastewater Treatment Facility Deep Injection Well No. 2

Glades WWTF Injection Well IW-2 Project No. 63-0007					Youngquist Brothers, LLC	
Selected	Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
	33	Setup and Perform Annular Pressure Test of IW-1	1	LS	\$50,000.00	\$50,000.00
	34	Setup and Perform Injection Test of IW-1	1	LS	\$150,000.00	\$150,000.00
	35	Furnish and Install Injection Well IW-2 Wellhead and Surface Facilities (Inc. Concrete Pad)	1	LS	\$650,000.00	\$650,000.00
	36	Furnish and Install Buried Piping, Valves and Fittings	1	LS	\$500,000.00	\$500,000.00
	37	General Sitework (Including Restoration)	1	LS	\$475,000.00	\$475,000.00
	38	Electrical and Instrumentation Work	1	LS	\$600,000.00	\$600,000.00
Base Bid Item NO.2 - Standby Time						
	39	Standby Time	60	HR	\$500.00	\$30,000.00
Total						\$0.00

SET AMOUNTS BY CITY

Owners Contingency

Set Amounts by City					Youngquist Brothers, LLC	
Selected	Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
	40	Owner's Contingency	1	LS	\$500,000.00	\$500,000.00
Total						\$0.00