

PLANT SCHEDULE MAIN CONTAINER CAL COMMON / BOTANICAL NAME NATIVE BALD CYPRESS / TAXODIUM DISTICHUM 4" CAL MIN. 14' HT., 6' SPR. YES FG, STRAIGHT, SÍNGLE LEADER, FULL, FL#1 EAST PALATKA HOLLY / ILEX X ATTENUATA 'EAST PALATKA' 4" CAL MIN. 14' HT., 6' SPR. F.G. NO FG, STRAIGHT, SINGLE LEADER, FULL QUEEN'S CRAPE MYRTLE / LAGERSTROEMIA SPECIOSA 4" CAL MIN. 14' HT., 6' SPR. YES SOUTHERN LIVE OAK / QUERCUS VIRGINIANA F.G. 4" CAL MIN. 14' HT., 6' SPR. YES FG, STRAIGHT, SINGLE LEADER, FULL, FL# 1 SOUTHERN MAGNOLIA / MAGNOLIA GRANDIFLORA F.G. 4" CAL MIN. 14' HT., 6' SPR. YES FG, STRAIGHT, SINGLE LEADER, FULL, FL#1 CABBAGE PALMETTO / SABAL PALMETTO F.G. 12**'**-14' HT YES MONTGOMERY PALM / VEITCHIA MONTGOMERYANA 12 CT NO COMMON / BOTANICAL NAME SPACING SIZE NATIVE CAPE JASMINE / GARDENIA JASMINOIDES 24" HT. MIN,, 24" SPR MIN. NO FULL TO GROUND CLUSIA NANA / CLUSIA ROSEA 'NANA' 24" HT. MIN,, 24" SPR MIN. YES FULL TO GROUND PODOCARPUS / PODOCARPUS MACROPHYLLUS 48" HT MIN., 24" SPR. MIN. YES FULL TO GROUND, MATCHING RED TIP COCOPLUM / CHRYSOBALANUS ICACO 'RED TIP' 24" HT MIN., 30" SPR MIN YES FULL TO GROUND CONFEDERATE JASMINE / TRACHELOSPERMUM JASMINOIDES 18" HT. MIN., 18" SPR. MIN. NO FULL TO GROUND COONTIE / ZAMIA PUMILA DWARF FKAHATCHEE / TRIPSACUM FLORIDANA 24" HT MIN., 24" SPR MIN. YES FULL TO GROUND GREEN ISLAND FICUS / FICUS MICROCARPA 'GREEN ISLAND' CONT 24" HT MIN., 24" SPR MIN. NO NATIVE SYMBOL CODE QTY COMMON / BOTANICAL NAME BRAZILIAN DWARF MORNING GLORY / EVOLVULUS GLOMERATUS 'BLUE DAZE' CONT 8" HT MIN., 10" SPR MIN NO

LANDSCAPE CALCULATIONS SITE PERIMETER LANDSCAPING REQUIREMENTS

PERENNIALL PEANUT / ARACHIS GLABRATA

100% INSECT/DIEASE FREE, LAID TIGHT, ROLLED

ST. AUGUSTINE GRASS / STENOTAPHRUM SECUNDATUM 'FLORATAM'

NORTH PROPERTY LINE ± 262 LF - 26 LF DRIVEWAY = ± 236 LF REQUIRED: 10' MINIMUM WIDTH 1 TREE PER 30 LF (1/30 x 236 LF = 8) 8 TREES REQUIRED A CONTINUOUS HEDGE

PROVIDED: 10' WIDE BUFFER AREA CONTINUOUS HEDGE

EAST PROPERTY LINE (VILLAGE PARKWAY)

10' MINIMUM WIDTH 1 TREE PER 30 LF (1/30 x 305 LF = 11) 11 TREES REQUIRED A CONTINUOUS HEDGE PROVIDED: 10' WIDE BUFFER AREA 11 TREES

SOUTH PROPERTY LINE (MARSHALL PARKWAY) ± 263 LF - 27 LF DRIVEWAY = ± 236 LF

10' MINIMUM WIDTH 1 TREE PER 30 LF (1/30 x 236 LF = 8) 8 TREES REQUIRED A CONTINUOUS HEDGE PROVIDED: 10' WIDE BUFFER AREA

CONTINUOUS HEDGE ± 283 LF - 56 LF DRIVEWAY = ± 227 LF

1 TREE PER 30 LF (1/30 x 227 LF = 8) 8 TREES REQUIRED A CONTINUOUS HEDGE 10' WIDE BUFFER AREA CONTINUOUS HEDGE

VEHICULAR USE AREA REQUIREMENTS REQUIRED:

1 SF OF LANDSCAPE AREA PER 18 SF OF VUA (34,023 SF VUA) 1,891 SF REQUIRED 180 SF MIN. PER AREA, 10' MIN. WIDTH WITH 1 TREE PER AREA 11 TREES REQUIRED SHRUBS AND GROUND COVER NOT TO EXCEED 3' H. PROVIDED: 2,650 SF OF VEHICULAR USE LANDSCAPE AREA

**BUILDING FACADE REQUIREMENTS** 

REQUIRED: 1 TREE OR PALM PER 30LF OF BUILDING 11 TREES/PALMS REQUIRED (322 LF LESS DRIVE THRU & BUILDING ACCESS) 1 SHRUB/ 2 LF OF BUILDING: 161 SHRUBS

PROVIDED: 11 MONTGOMERY PALMS

216 TOTAL SHRUBS (CAPE JASMINE, RED TIP COCOPLUM, CONFEDERATE JASMINE, GREEN ISLAND FICUS)

OFF-STREET LOADING AND WASTE SCREENING

A CONTINUOUS EVERGREEN HEDGE THAT IS AT LEAST 48" IN HEIGHT PROVIDED:

CONTINUOUS 48" HEIGHT PODOCARPUS HEDGE AROUND ALL LOADING AND DUMPSTER **ENCLOSURES** 

LANDSCAPE REQUIREMENTS TREE REQUIREMENTS

57 TREES REQUIRED / 5 SPECIES REQUIRED 69 TREES PROVIDED / 7 SPECIES PROVIDED

FLOWERING TREE REQUIREMENT 20% REQUIRED TO BE FLOWERING 11 OF 57 TREES REQUIRED TO BE FLOWERING 13 FLOWERING TREES PROVIDED (MAGNOLIA & QUEEN'S CRAPE MYRTLE)

NATIVE TREE REQUIREMENT 50% OF REQUIRED TREES TO BE FLORIDA NATIVE 42 OF 69 TREES (61%) ARE FLORIDA NATIVES

PALM TREE REQUIREMENT 25% MAX. OF REQUIRED TREES MAY BE PALM SPECIES (LESS BUILDING FACADE) 16 PALMS PROVIDED OUTSIDE OF BUILDING FACADE: 16 / 69 = 23%

SHRUB REQUIREMENT 1,632 TOTAL SHRUBS PROVIDED 25% OF SHRUBS MUST BE FLORIDA NATIVES 1,025 SHRUBS PROVIDED ARE FLORIDA NATIVES: 1,030 / 1,632 = 63% LAWN REQUIREMENT

MAX OF 50% OF SITE LANDSCAPING ALLOWED TO BE LAWN TOTAL SITE LANDSCAPING: 30,664 SF \* 50% = 15,332 SF REQUIRED: MAX:15,332 SF OF LAWN PROVIDED: 13,310 SF OF ST. AUGUSTINE 'FLORATAM' (45%)

HATCH LEGEND

VEHICLE USE AREA (34,023 SF)

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED ON THIS PROJECT. ONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE.

ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF

1988 (NAVD '88). SUBTRACT 1.47' FROM NGVD '29 ELEVATION TO GET THE NAVD '88 ELEVATION



Know what's below. Call before you dig.

CITY OF PORT ST. LUCIE PROJECT P23-189 PSLUSD PROJECT# 5436

SHEET NUMBER

YES

© 74

\* 103/

S

GROV


THERN


SOU

ENS

Ш

.GR






GRAPHIC SCALE IN FEET

0 24.

SOUTHERN GROVE WALGREENS AT Know what's below. Call before you dig.

TY OF PORT ST. LUCIE PROJECT P23-189 PSLUSD PROJECT # 5436

SHEET NUMBER L-101



EXCAVATE CONTINUOUS 36" DEEP (FROM TOP OF CURB) FOR ENTIRE LENGTH AND WIDTH OF ISLAND &

PROTECT AND RETAIN ALL CURBS AND BASE. COMPACTED SUBGRADE TO REMAIN FOR STRUCTURAL

ALL ISLANDS SHALL UTILIZE POOR DRAINAGE DETAIL WHEN PERCOLATION RATES ARE 2" PER HOUR OR

BACKFILL WITH APPROVED PLANTING MIX.

Planted Parking Lot Islands / Medians

SUPPORT OF CURB SYSTEM (TYP).

PARKING ISLAND, NOSE-IN DETAIL

2. CURB OR PARKING LOT EDGE, BY OTHERS

Parking Space/Curb Planting

1. INSTALL CONTINUOUS MULCH BED ADJACENT TO PARKING SPACES AS SHOWN, MULCH SHALL BE MIN, 3" DEEP.

NO POP-UP IRRIGATION HEADS SHALL BE LOCATED WITHIN 24" OF A PARKING SPACE ON ANY SIDE

\* CLEAR ZONE: 36" MIN. FROM BUILDING TO CENTER OF NEAREST SHRUB.

NO TREES SHALL BE PLACED WITHIN SHOWN RADIUS OF ALL PROPOSED OR EXISTING FIRE HYDRANTS.

3 PROVIDE A MULCH, 3" DEPTH MIN., SURROUNDING AREA INDICATED.

Fire Hydrant Clear Zone

CONTRACTOR SHALL ADJUST PLANT MATERIAL SO THAT NO CONFLICTS WITH FIRE HYDRANTS OCCUR

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED ON THIS PROJECT. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE.

ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF

1988 (NAVD '88). SUBTRACT 1.47' FROM NGVD '29 ELEVATION TO GET THE NAVD '88 ELEVATION

3-4" GRAVEL

Know what's below. Call before you dig.

ITY OF PORT ST. LUCIE PROJECT P23-189 PSLUSD PROJECT#

5436

GROV

EENS

.GR

SHEET NUMBER

© 74

### GENERAL LANDSCAPE SPECIFICATIONS AND NOTES

### A. SCOPE OF WORK

1. THE WORK CONSISTS OF: FURNISHING ALL LABOR, MATERIALS, EQUIPMENT, TOOLS, TRANSPORTATION, AND ANY OTHER APPURTENANCES NECESSARY FOR THE COMPLETION OF THIS PROJECT AS SHOWN ON THE DRAWINGS, AS INCLUDED IN THE PLANT LIST, AND AS HEREIN SPECIFIED.

2. WORK SHALL INCLUDE MAINTENANCE AND WATERING OF ALL CONTRACT PLANTING AREAS UNTIL CERTIFICATION OF ACCEPTABILITY BY THE OWNER.

### B. PROTECTION OF EXISTING STRUCTURES

ALL EXISTING BUILDINGS, WALKS, WALLS, PAVING, PIPING, OTHER SITE CONSTRUCTION ITEMS, AND PLANTING ALREADY COMPLETED OR ESTABLISHED SHALL BE PROTECTED FROM DAMAGE BY THE CONTRACTOR UNLESS OTHERWISE SPECIFIED. ALL DAMAGE RESULTING FROM NEGLIGENCE SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE OWNER, AT NO COST TO THE OWNER.

### C. PROTECTION OF EXISTING PLANT MATERIALS OUTSIDE LIMIT OF WORK

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL UNAUTHORIZED CUTTING OR DAMAGE TO TREES AND SHRUBS EXISTING OR OTHERWISE, CAUSED BY CARELESS EQUIPMENT OPERATION, MATERIAL STOCKPILING, ETC. THIS SHALL INCLUDE COMPACTION BY DRIVING OR PARKING INSIDE THE DRIP-LINE AND SPILLING OIL, GASOLINE, OR OTHER DELETERIOUS MATERIALS WITHIN THE DRIP-LINE. NO MATERIALS SHALL BE BURNED WHERE HEAT WILL DAMAGE ANY PLANT. EXISTING TREES KILLED OR DAMAGED SO THAT THEY ARE MISSHAPEN AND/ OR UNSIGHTLY SHALL BE REPLACED AT THE COST TO THE CONTRACTOR OF ONE HUNDRED DOLLARS (\$100) PER CALIPER INCH ON AN ESCALATING SCALE WHICH ADDS AN ADDITIONAL TWENTY (20) PERCENT PER INCH OVER FOUR (4) INCHES CALIPER AS FIXED AND AGREED LIQUIDATED DAMAGES. CALIPER SHALL BE MEASURED SIX (6) INCHES ABOVE GROUND LEVEL FOR TREES UP TO AND INCLUDING FOUR (4) INCHES IN CALIPER AND TWELVE (12) INCHES ABOVE GROUND LEVEL FOR TREES OVER FOUR (4) INCHES IN CALIPER.

### D. MATERIALS

MATERIALS LISTED BELOW SHALL BE SUBMITTED FOR APPROVAL. UPON SUBMITTALS' APPROVAL, DELIVERY OF

# MATERIALS MAY COMMENCE.

TOPSOIL MIX AMENDMENT MIX/ PRODUCT DATA/ TEST RESULTS PLANTS PHOTOGRAPHS OF ONE (1) OF EACH SPECIES (OR TAGGED IN NURSERY) INDICATE SIZES (HEIGHT/WIDTH) AND QUALITY PER SPEC.

### CLIENT-REQUESTED TAGGING MAY SUBSTITUTE PHOTOS. FERTILIZER PRODUCT DATA

### INNOCULANT PRODUCT DATA HERBICIDE PRODUCT DATA

A. PLANT SPECIES AND SIZE SHALL CONFORM TO THOSE INDICATED ON THE DRAWINGS. NOMENCLATURE SHALL CONFORM TO STANDARDIZED PLANT NAMES, 1942 EDITION. ALL NURSERY STOCK SHALL BE IN ACCORDANCE WITH GRADES AND STANDARDS FOR NURSERY PLANTS, LATEST EDITION, PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES. ALL PLANTS SHALL BE FLORIDA GRADE NO. 1 OR BETTER AS DETERMINED BY THE FLORIDA DIVISION OF PLANT INDUSTRY. ALL PLANTS SHALL BE HEALTHY, VIGOROUS, SOUND. WELL-BRANCHED, AND FREE OF DISEASE AND INSECTS, INSECT EGGS AND LARVAE AND SHALL HAVE ADEQUATE ROOT SYSTEMS. TREES FOR PLANTING IN ROWS SHALL BE UNIFORM IN SIZE AND SHAPE. ALL MATERIALS SHALL BE SUBJECT TO APPROVAL BY THE OWNER. WHERE ANY REQUIREMENTS ARE OMITTED FROM THE PLANT LIST, THE PLANTS FURNISHED SHALL BE NORMAL FOR THE VARIETY. PLANTS SHALL BE PRUNED PRIOR TO DELIVERY ONLY WITH APPROVAL FROM OWNER OR OWNER'S REPRESENTATIVE. NO SUBSTITUTIONS SHALL BE MADE WITHOUT WRITTEN PERMISSION FROM THE OWNER'S REPRESENTATIVE

B. MEASUREMENTS: THE HEIGHT AND/OR WIDTH OF TREES SHALL BE MEASURED FROM THE GROUND OR ACROSS THE NORMAL SPREAD OF BRANCHES WITH THE PLANTS IN THEIR NORMAL POSITION. THIS MEASUREMENT SHALL NOT INCLUDE THE IMMEDIATE TERMINAL GROWTH. PLANTS LARGER IN SIZE THAN THOSE SPECIFIED IN THE PLANT LIST MAY BE USED IF APPROVED BY THE OWNER. IF THE USE OF LARGER PLANTS IS APPROVED, THE BALL OF EARTH OR SPREAD OF ROOTS SHALL BE INCREASED IN PROPORTION TO THE SIZE OF THE PLANT.

C. INSPECTION: PLANTS SHALL BE SUBJECT TO INSPECTION AND APPROVAL AT THE PLACE OF GROWTH, OR UPON DELIVERY TO THE SITE, AS DETERMINED BY THE OWNER, FOR QUALITY, SIZE, AND VARIETY; SUCH APPROVAL SHALL NOT IMPAIR THE RIGHT OF INSPECTION AND REJECTION AT THE SITE DURING PROGRESS OF THE WORK OR AFTER COMPLETION FOR SIZE AND CONDITION OF ROOT BALLS OR ROOTS, LATENT DEFECTS OR INJURIES. REJECTED PLANTS SHALL BE REMOVED IMMEDIATELY FROM THE SITE. NOTICE REQUESTING INSPECTION SHALL BE SUBMITTED IN WRITING BY THE CONTRACTOR AT LEAST ONE (1) WEEK PRIOR TO ANTICIPATED DATE.

## E. SOIL MIXTURE (PLANTING MEDIUM, PLANTING MIX, MIX)

- 1. SOIL MIXTURE SHALL CONSIST OF 70% COARSE SAND, 30% FLORIDA PEAT AS DESCRIBED BELOW.
- 2. SOIL FOR USE IN PREPARING SOIL MIXTURE FOR BACKFILLING SHALL BE FERTILE, FRIABLE, AND REASONABLY FREE OF SUBSOIL, CLAY LUMPS, BRUSH WEED AND OTHER LITTER, FREE OF ROOTS. STUMPS, STONE LARGER THAN 2" IN ANY DIRECTION, AND OTHER EXTRANEOUS OR TOXIC MATTER HARMFUL TO PLANT GROWTH. IT SHALL HAVE A PH BETWEEN 5.5 AND 7.0 - SUBMIT SAMPLE AND PH TESTING RESULTS FOR APPROVAL.
- SAND SHALL BE COARSE, CLEAN, WELL-DRAINING, NATIVE ORTONA MINED SAND. CONTRACTOR SHALL SUBMIT RESULTS OF SOIL TEST FOR PEAT AND SAND PROPOSED FOR USE UNDER THIS CONTRACT FOR APPROVAL.
- 4. CONTRACTOR SHALL SUBMIT SAMPLES OF SOIL MIXTURE FOR LANDSCAPE ARCHITECT REVIEW UNDER FORMAL SUBMITTAL AND SUBSEQUENTLY TO OWNER'S REPRESENTATIVE THEREAFTER FOR APPROVAL PRIOR TO PLANT INSTALLATION OPERATIONS COMMENCE.
- 5. FLORIDA MUCK / FLORIDA MUCKY PEAT MAY BE PROVIDED AS A SUBSTITUTE FOR THE 30% FLORIDA PEAT, CONTINGENT UPON PRELIMINARY TEST RESULTS AND AS DETERMINED BY THE LANDSCAPE ARCHITECT DURING THE SUBMITTAL PROCESS. ANY CHANGES IN THE PERCENTAGES OR PARENT MATERIALS REQUIRED TO PROVIDE THE SPECIFIED MIXTURE AS DETERMINED BY THE LANDSCAPE ARCHITECT SHALL BE PROVIDED BY THE CONTRACTOR AT NO ADDITIONAL COST TO OWNER.
- 6. CONTRACTOR SHALL PROVIDE PHITEST RESULTS FOR ALL MIX COMPONENTS AND FINAL MIX.
- 7. CONTRACTOR SHALL PROVIDE PENETROMETER ON-SITE AT ALL TIMES FOR COMPACTION INSPECTION AT THE DISCRETION OF THE LANDSCAPE ARCHITECT.
- 8. PENETROMETER CRITERIA / SPECIFICATIONS SHALL RANGE FROM APPROX. 75 PSI TO LESS THAN 300 PSI OR AS DETERMINED BY THE LANDSCAPE ARCHITECT.
- 9. FINAL MIX SHALL BE TESTED TO HAVE A SATURATED WEIGHT OF NO MORE THAN 85 POUNDS PER CUBIC FOOT WHEN COMPACTED TO 85% STANDARD PROCTOR. FERTILIZER PRODUCT DATA AND RATE SCHEDULE SHALL BE SUBMITTED CONCURRENTLY WITH THE SOIL SUBMITTAL FOR EVALUATION BY THE LANDSCAPE ARCHITECT.
- 10. SOIL SHALL BE SUPPLIED BY ATLAS PEAT & SOIL INC. 9621 STATE ROAD, BOYNTON BEACH, FLORIDA 33472 PHONE: 561-734-7300.

WATER NECESSARY FOR PLANTING AND MAINTENANCE SHALL BE OF SATISFACTORY QUALITY TO SUSTAIN AN ADEQUATE PLANT GROWTH AND SHALL NOT CONTAIN HARMFUL, NATURAL OR MAN-MADE ELEMENTS DETRIMENTAL TO PLANTS. WATER MEETING THE ABOVE STANDARD SHALL BE OBTAINED ON THE SITE FROM THE OWNER, IF AVAILABLE, AND THE CONTRACTOR SHALL BE RESPONSIBLE TO MAKE ARRANGEMENTS FOR ITS USE BY HIS TANKS, HOSES, SPRINKLERS, ETC.. IF SUCH WATER IS NOT AVAILABLE AT THE SITE, THE CONTRACTOR SHALL PROVIDE SATISFACTORY WATER FROM SOURCES OFF THE SITE AT NO ADDITIONAL COST TO THE OWNER.

\*WATERING/IRRIGATION RESTRICTIONS MAY APPLY - REFER TO PROPERTY'S JURISDICTIONAL AUTHORITY.

### G. FERTILIZER

CONTRACTOR SHALL PROVIDE FERTILIZER APPLICATION SCHEDULE TO OWNER, AS APPLICABLE TO SOIL TYPE, PLANT INSTALLATION TYPE, AND SITE'S PROPOSED USE. SUGGESTED FERTILIZER TYPES SHALL BE ORGANIC OR OTHERWISE NATURALLY-DERIVED.

\*FERTILIZER RESTRICTIONS MAY APPLY - REFER TO PROPERTY'S JURISDICTIONAL AUTHORITY.

## H. ROCK MULCH

ROCK MULCH MATERIAL SHALL BE TWO (2) TO THREE (3) INCHES DIAMETER CHATTAHOOCHEE ROCK (OR APPROVED EQUAL) AT A MINIMUM DEPTH OF THREE (3) INCHES IN ALL LANDSCAPE SHRUB AND GROUNDCOVER AREAS. THE ROCK MULCH SHALL CONFINE TO THE LANDSCAPE BED LINES ESTABLISHED BY ADJACENT SOD AREAS, HARDSCAPE AREAS, AND CURBS. CLEAR MULCH FROM EACH PLANT'S CROWN (BASE).

## I. DIGGING AND HANDLING

- 1. PROTECT ROOTS OR ROOT BALLS OF PLANTS AT ALL TIMES FROM SUN, DRYING WINDS, WATER AND FREEZING, AS NECESSARY UNTIL PLANTING. PLANT MATERIALS SHALL BE ADEQUATELY PACKED TO PREVENT DAMAGE DURING TRANSIT. TREES TRANSPORTED MORE THAN TEN (10) MILES OR WHICH ARE NOT PLANTED WITHIN THREE (3) DAYS OF DELIVERY TO SITE SHALL BE SPRAYED WITH AN ANTITRANSPIRANT PRODUCT ("WILTPRUF" OR EQUAL) TO MINIMIZE TRANSPIRATIONAL WATER LOSS.
- 2. BALLED AND BURLAPPED PLANTS (B&B) SHALL BE DUG WITH FIRM, NATURAL BALLS OF SOIL OF SUFFICIENT SIZE TO ENCOMPASS THE FIBROUS AND FEEDING ROOTS OF THE PLANTS. NO PLANTS MOVED WITH A ROOT BALL SHALL BE PLANTED IF THE BALL IS CRACKED OR BROKEN. PLANTS BALLED AND BURLAPPED OR CONTAINER GROWN SHALL
- 3. PLANTS MARKED "BR" IN THE PLANT LIST SHALL BE DUG WITH BARE ROOTS, COMPLYING WITH FLORIDA GRADES AND STANDARDS FOR NURSERY PLANTS, CURRENT EDITION. CARE SHALL BE EXERCISED THAT THE ROOTS DO NOT DRY OUT DURING TRANSPORTATION AND PRIOR TO PLANTING.
- 4. PROTECTION OF PALMS (IF APPLICABLE): ONLY A MINIMUM OF FRONDS SHALL BE REMOVED FROM THE CROWN OF THE PALM TREES TO FACILITATE MOVING AND HANDLING. CLEAR TRUNK (CT) SHALL BE AS SPECIFIED AFTER THE MINIMUM OF FRONDS HAVE BEEN REMOVED. ALL PALMS SHALL BE BRACED PER PALM PLANTING DETAIL.
- 5. EXCAVATION OF TREE PITS SHALL BE PERFORMED USING EXTREME CARE TO AVOID DAMAGE TO SURFACE AND SUBSURFACE ELEMENTS SUCH AS UTILITIES OR HARDSCAPE ELEMENTS, FOOTERS AND PREPARED SUB-BASES.

### J. CONTAINER GROWN STOCK

- 1. ALL CONTAINER GROWN MATERIAL SHALL BE HEALTHY, VIGOROUS, WELL-ROOTED PLANTS ESTABLISHED IN THE CONTAINER IN WHICH THEY ARE SOLD. THE PLANTS SHALL HAVE TOPS WHICH ARE OF GOOD QUALITY AND ARE IN A HEALTHY GROWING CONDITION, FLORIDA #1 OR BETTER.
- 2. AN ESTABLISHED CONTAINER GROWN PLANT SHALL BE TRANSPLANTED INTO A CONTAINER AND GROWN IN THAT CONTAINER SUFFICIENTLY LONG FOR THE NEW FIBROUS ROOTS TO HAVE DEVELOPED SO THAT THE ROOT MASS WILL RETAIN ITS SHAPE AND HOLD TOGETHER WHEN REMOVED FROM THE CONTAINER. CONTAINER GROWN STOCK SHALL NOT BE HANDLED BY THEIR STEMS.

### 3. PLANT ROOTS BOUND IN CONTAINERS ARE NOT ACCEPTABLE.

4. SUBSTITUTION OF NON-CONTAINER GROWN MATERIAL FOR MATERIAL EXPLICITLY SPECIFIED TO BE CONTAINER GROWN WILL NOT BE PERMITTED WITHOUT WRITTEN APPROVAL IS OBTAINED FROM THE OWNER OR OWNER'S REPRESENTATIVE.

## K. COLLECTED STOCK

WHEN THE USE OF COLLECTED STOCK IS PERMITTED AS INDICATED BY THE OWNER OR OWNER'S REPRESENTATIVE, THE MINIMUM SIZES OF ROOTBALLS SHALL BE EQUAL TO THAT SPECIFIED FOR THE NEXT LARGER SIZE OF NURSERY GROWN STOCK OF THE SAME VARIETY.

## L. NATIVE STOCK

PLANTS COLLECTED FROM WILD OR NATIVE STANDS SHALL BE CONSIDERED NURSERY GROWN WHEN THEY HAVE BEEN SUCCESSFULLY RE-ESTABLISHED IN A NURSERY ROW AND GROWN UNDER REGULAR NURSERY CULTURAL PRACTICES FOR A MINIMUM OF TWO (2) GROWING SEASONS AND HAVE ATTAINED ADEQUATE ROOT AND TOP GROWTH TO INDICATE FULL RECOVERY FROM TRANSPLANTING INTO THE NURSERY ROW.

## M. MATERIALS LIST

QUANTITIES NECESSARY TO COMPLETE THE WORK ON THE DRAWINGS SHALL BE FURNISHED BY THE CONTRACTOR. QUANTITY ESTIMATES HAVE BEEN MADE CAREFULLY, BUT THE LANDSCAPE ARCHITECT OR OWNER ASSUMES NO LIABILITY FOR OMISSIONS OR ERRORS. SHOULD A DISCREPANCY OCCUR BETWEEN THE PLANS AND THE PLANT LIST QUANTITY, THE LANDSCAPE ARCHITECT SHALL BE NOTIFIED FOR CLARIFICATION PRIOR TO BIDDING OR INSTALLATION. ALL DIMENSIONS AND/OR SIZES SPECIFIED SHALL BE THE MINIMUM ACCEPTABLE SIZE

## N. FINE GRADING

- 1. FINE GRADING UNDER THIS CONTRACT SHALL CONSIST OF FINAL FINISHED GRADING OF LAWN AND PLANTING AREAS THAT HAVE BEEN ROUGH GRADED BY OTHERS. BERMING AS SHOWN ON THE DRAWINGS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, UNLESS OTHERWISE NOTED.
- 2. THE CONTRACTOR SHALL FINE GRADE THE LAWN AND PLANTING AREAS TO BRING THE ROUGH GRADE UP TO FINAL FINISHED GRADE ALLOWING FOR THICKNESS OF SOD AND/OR MULCH DEPTH. THIS CONTRACTOR SHALL FINE GRADE BY HAND AND/OR WITH ALL EQUIPMENT NECESSARY INCLUDING A GRADING TRACTOR WITH FRONT-END LOADER FOR TRANSPORTING SOIL WITHIN THE SITE.
- 3. ALL PLANTING AREAS SHALL BE GRADED AND MAINTAINED FOR POSITIVE DRAINAGE TO SURFACE/SUBSURFACE STORM DRAIN SYSTEMS. AREAS ADJACENT TO BUILDINGS SHALL SLOPE AWAY FROM THE BUILDINGS. REFER TO CIVIL ENGINEER'S PLANS FOR FINAL GRADES.

## O. PLANTING PROCEDURES

- 1. CLEANING UP BEFORE COMMENCING WORK: THE CONTRACTOR SHALL CLEAN WORK AND SURROUNDING AREAS OF ALL RUBBISH OR OBJECTIONABLE MATTER. ALL MORTAR, CEMENT, AND TOXIC MATERIAL SHALL BE REMOVED FROM THE SURFACE OF ALL PLANT BEDS. THESE MATERIALS SHALL NOT BE MIXED WITH THE SOIL. SHOULD THE CONTRACTOR FIND SUCH SOIL CONDITIONS BENEATH THE SOIL WHICH WILL IN ANY WAY ADVERSELY AFFECT THE PLANT GROWTH, HE SHALL IMMEDIATELY CALL IT TO THE ATTENTION OF THE OWNER'S REPRESENTATIVE. FAILURE TO DO SO BEFORE PLANTING SHALL MAKE THE CORRECTIVE MEASURES THE RESPONSIBILITY OF THE CONTRACTOR.
- 2, VERIFY LOCATIONS OF ALL UTILITIES, CONDUITS, SUPPLY LINES AND CABLES, INCLUDING BUT NOT LIMITED TO: ELECTRIC, GAS (LINES AND TANKS), WATER, SANITARY SEWER, STORMWATER SYSTEMS, CABLE, AND TELEPHONE. PROPERLY MAINTAIN AND PROTECT EXISTING UTILITIES. CALL NATIONAL ONE CALL -811 - TO LOCATE UTILITIES.

- 3. SUBGRADE EXCAVATION: CONTRACTOR IS RESPONSIBLE TO REMOVE ALL EXISTING AND IMPORTED LIMEROCK AND LIMEROCK SUB-BASE FROM ALL LANDSCAPE PLANTING AREAS TO A MINIMUM DEPTH OF 36". CONTRACTOR IS RESPONSIBLE TO BACKFILL THESE PLANTING AREAS TO ROUGH FINISHED GRADE WITH CLEAN TOPSOIL FROM AN ON-SITE SOURCE OR AN IMPORTED SOURCE. IF LIMEROCK OR OTHER ADVERSE CONDITIONS OCCUR IN PLANTED AREAS AFTER 36" DEEP EXCAVATION BY THE CONTRACTOR, AND ADEQUATE PERCOLATION CAN NOT BE ACHIEVED, CONTRACTOR SHALL UTILIZE PLANTING DETAIL THAT ADDRESSES POOR DRAINAGE.
- 4. FURNISH NURSERY'S CERTIFICATE OF COMPLIANCE WITH ALL REQUIREMENTS AS HEREIN SPECIFIED AND REQUIRED. INSPECT AND SELECT PLANT MATERIALS BEFORE PLANTS ARE DUG AT NURSERY OR GROWING SITE.
- 5. GENERAL: COMPLY WITH APPLICABLE FEDERAL, STATE, COUNTY. AND LOCAL REGULATIONS GOVERNING LANDSCAPE MATERIALS AND WORK. CONFORM TO ACCEPTED HORTICULTURAL PRACTICES AS USED IN THE TRADE. UPON ARRIVAL AT THE SITE, PLANTS SHALL BE THOROUGHLY WATERED AND PROPERLY MAINTAINED UNTIL PLANTED. PLANTS STORED ON-SITE SHALL NOT REMAIN UNPLANTED FOR A PERIOD EXCEEDING TWENTY-FOUR (24) HOURS. AT ALL TIMES, METHODS CUSTOMARY IN GOOD HORTICULTURAL PRACTICES SHALL BE EXERCISED.
- 6. THE WORK SHALL BE COORDINATED WITH OTHER TRADES TO PREVENT CONFLICTS. COORDINATE PLANTING WITH IRRIGATION WORK TO ASSURE AVAILABILITY OF WATER AND PROPER LOCATION OF IRRIGATION APPURTENANCES
- 7. ALL PLANTING PITS SHALL BE EXCAVATED TO SIZE AND DEPTH IN ACCORDANCE WITH THE USA STANDARD FOR NURSERY STOCK 260.1, UNLESS SHOWN OTHERWISE ON THE DRAWINGS, AND BACKFILLED WITH THE PREPARED PLANTING SOIL MIXTURE AS SPECIFIED IN SECTION E. TEST ALL TREE PITS WITH WATER BEFORE PLANTING TO ASSURE PROPER DRAINAGE PERCOLATION IS AVAILABLE. NO ALLOWANCE WILL BE MADE FOR LOST PLANTS DUE TO IMPROPER PERCOLATION. IF POOR PERCOLATION EXISTS, UTILIZE "POOR DRAINAGE CONDITION" PLANTING DETAIL. TREES SHALL BE SET PLUMB AND HELD IN POSITION UNTIL THE PLANTING MIXTURE HAS BEEN FLUSHED INTO PLACE WITH A SLOW, FULL HOSE STREAM. ALL PLANTING SHALL BE PERFORMED BY PERSONNEL FAMILIAR WITH PLANTING PROCEDURES AND UNDER THE SUPERVISION OF A QUALIFIED LANDSCAPE FOREMAN. PROPER "JETTING IN" SHALL BE ASSURED TO ELIMINATE AIR POCKETS AROUND THE ROOTS. "JET STICK" OR EQUAL IS RECOMMENDED.
- 8. TAKE ALL NECESSARY PRECAUTIONS TO AVOID DAMAGE TO BUILDINGS AND BUILDING STRUCTURES WHILE INSTALLING TREES.
- 9. SOIL MIXTURE SHALL BE AS SPECIFIED IN SECTION E OF THESE SPECIFICATIONS.
- 10. TREES AND SHRUBS SHALL BE SET STRAIGHT AT AN ELEVATION THAT. AFTER SETTLEMENT, THE PLANT CROWN WILL STAND ONE (1) TO TWO (2) INCHES ABOVE GRADE. EACH PLANT SHALL BE SET IN THE CENTER OF THE PIT. PLANTING SOIL MIXTURE SHALL BE BACKFILLED, THOROUGHLY TAMPED AROUND THE BALL, AND SETTLED BY WATER (AFTER TAMPING).
- 11. AMEND PINE AND OAK PLANT PITS WITH ECTOMYCORRHIZAL SOIL APPLICATION PER MANUFACTURER'S RECOMMENDATION. ALL OTHER PLANT PITS SHALL BE AMENDED WITH ENDOMYCORRHIZAL SOIL APPLICATION PER MANUFACTURER'S RECOMMENDATION. PROVIDE PRODUCT INFORMATION SUBMITTAL PRIOR TO INOCULATION.
- 12. FILL HOLE WITH SOIL MIXTURE, MAKING CERTAIN ALL SOIL IS SATURATED. TO DO THIS, FILL HOLE WITH WATER AND ALLOW TO SOAK MINIMUM TWENTY (20) MINUTES, STIRRING IF NECESSARY TO GET SOIL THOROUGHLY WET. PACK LIGHTLY WITH FEET. ADD MORE WET SOIL MIXTURE. DO NOT COVER TOP OF BALL WITH SOIL MIXTURE, ONLY WITH MULCH. ALL BURLAP, ROPE, WIRES, BASKETS, ETC.., SHALL BE REMOVED FROM THE SIDES AND TOPS OF BALLS, BUT NO BURLAP SHALL BE PULLED FROM UNDERNEATH.
- 13. PRUNING: TREES SHALL BE PRUNED, AT THE DIRECTION OF THE OWNER OR OWNER'S REPRESENTATIVE, TO PRESERVE THE NATURAL CHARACTER OF THE PLANT. ALL SOFT WOOD OR SUCKER GROWTH AND ALL BROKEN OR BADLY DAMAGED BRANCHES SHALL BE REMOVED WITH A CLEAN CUT. ALL PRUNING TO BE PERFORMED BY LICENSED ARBORIST, IN ACCORDANCE WITH ANSI A-300.
- 14. SHRUBS AND GROUND COVER PLANTS SHALL BE EVENLY SPACED IN ACCORDANCE WITH THE DRAWINGS AND AS INDICATED ON THE PLANT LIST. CULTIVATE ALL PLANTING AREAS TO A MINIMUM DEPTH OF 6", REMOVE AND DISPOSE ALL DEBRIS. MIX TOP 4" TO ACHEIVE SOIL MIXTURE AS SPECIFIED IN SECTION E. THOROUGHLY WATER ALL PLANTS AFTER INSTALLATION.
- 15. TREE GUYING AND BRACING SHALL BE INSTALLED BY THE CONTRACTOR IN ACCORDANCE WITH THE PLANS TO INSURE STABILITY AND MAINTAIN TREES IN AN UPRIGHT POSITION. IF THE CONTRACTOR AND OWNER DECIDE TO WAIVE THE TREE GUYING AND BRACING, THE OWNER SHALL NOTIFY THE LANDSCAPE ARCHITECT IN WRITING AND AGREE TO INDEMNIFY AND HOLD HARMLESS THE LANDSCAPE ARCHITECT IN THE EVENT UNSUPPORTED TREES PLANTED UNDER THIS CONTRACT FALL AND DAMAGE PERSON OR PROPERTY.
- 16. MULCHING: PROVIDE A THREE INCH (MINIMUM) LAYER OF SPECIFIED MULCH OVER THE ENTIRE AREA OF EACH SHRUB BED, GROUND COVER, VINE BED, AND TREE PIT PLANTED UNDER THIS CONTRACT.
- 17. HERBICIDE WEED CONTROL: ALL PLANT BEDS SHALL BE KEPT FREE OF NOXIOUS WEEDS UNTIL FINAL ACCEPTANCE OF WORK. IF DIRECTED BY THE OWNER, "ROUND-UP" SHALL BE APPLIED FOR WEED CONTROL BY QUALIFIED PERSONNEL TO ALL PLANTING AREAS IN SPOT APPLICATIONS PER MANUFACTURER'S PRECAUTIONS AND SPECIFICATIONS. PRIOR TO FINAL INSPECTION. TREAT ALL PLANTING BEDS WITH AN APPROVED PRE-EMERGENT HERBICIDE AT AN APPLICATION RATE RECOMMENDED BY THE MANUFACTURER. (AS ALLOWED BY JURISDICTIONAL AUTHORITY)

## P. LAWN SODDING

- 1. THE WORK CONSISTS OF LAWN BED PREPARATION, SOIL PREPARATION, AND SODDING COMPLETE, IN STRICT ACCORDANCE WITH THE SPECIFICATIONS AND THE APPLICABLE DRAWINGS TO PRODUCE A TURF GRASS LAWN ACCEPTABLE TO THE OWNER.
- 2. LAWN BED PREPARATION: ALL AREAS THAT ARE TO BE SODDED SHALL BE CLEARED OF ANY ROUGH GRASS, WEEDS, AND DEBRIS, AND THE GROUND BROUGHT TO AN EVEN GRADE. THE ENTIRE SURFACE SHALL BE ROLLED WITH A ROLLER WEIGHING NOT MORE THAN ONE-HUNDRED (100) POUNDS PER FOOT OF WIDTH. DURING THE ROLLING, ALL DEPRESSIONS CAUSED BY SETTLEMENT SHALL BE FILLED WITH ADDITIONAL SOIL, AND THE SURFACE SHALL BE REGRADED AND ROLLED UNTIL PRESENTING A SMOOTH AND EVEN FINISH TO THE REQUIRED GRADE.
- 3. SOIL PREPARATION: PREPARE LOOSE BED FOUR (4) INCHES DEEP. HAND RAKE UNTIL ALL BUMPS AND DEPRESSIONS ARE REMOVED. WET PREPARED AREA THOROUGHLY.

- A. THE CONTRACTOR SHALL SOD ALL AREAS THAT ARE NOT PAVED OR PLANTED AS DESIGNATED ON THE DRAWINGS WITHIN THE CONTRACT LIMITS, UNLESS SPECIFICALLY NOTED OTHERWISE.
- B. THE SOD SHALL BE CERTIFIED TO MEET FLORIDA STATE PLANT BOARD SPECIFICATIONS, ABSOLUTELY TRUE TO VARIETAL TYPE, AND FREE FROM WEEDS, FUNGUS, INSECTS AND DISEASE OF ANY KIND.
- C. SOD PANELS SHALL BE LAID TIGHTLY TOGETHER SO AS TO MAKE A SOLID SODDED LAWN AREA. SOD SHALL BE LAID UNIFORMLY AGAINST THE EDGES OF ALL CURBS AND OTHER HARDSCAPE ELEMENTS, PAVED AND PLANTED AREAS. ADJACENT TO BUILDINGS, A 24 INCH STONE MULCH STRIP SHALL BE PROVIDED - REFER TO DETAILS. IMMEDIATELY FOLLOWING SOD LAYING, THE LAWN AREAS SHALL BE ROLLED WITH A LAWN ROLLER CUSTOMARILY USED FOR SUCH PURPOSES, AND THEN THOROUGHLY IRRIGATED. IF, IN THE OPINION OF THE OWNER, TOP-DRESSING IS NECESSARY AFTER ROLLING TO FILL THE VOIDS BETWEEN THE SOD PANELS AND TO EVEN OUT INCONSISTENCIES IN THE SOD, CLEAN SAND, AS APPROVED BY THE OWNER'S REPRESENTATIVE. SHALL BE UNIFORMLY SPREAD OVER THE ENTIRE SURFACE OF THE SOD AND THOROUGHLY WATERED IN. FERTILIZE INSTALLED SOD AS ALLOWED BY PROPERTY'S JURISDICTIONAL AUTHORITY.
- 5. DURING DELIVERY, PRIOR TO, AND DURING THE PLANTING OF THE LAWN AREAS, THE SOD PANELS SHALL AT ALL TIMES BE PROTECTED FROM EXCESSIVE DRYING AND UNNECESSARY EXPOSURE OF THE ROOTS TO THE SUN. ALL SOD SHALL BE STACKED SO AS NOT TO BE DAMAGED BY SWEATING OR EXCESSIVE HEAT AND MOISTURE.

- A. WITHIN THE CONTRACT LIMITS, THE CONTRACTOR SHALL PRODUCE A DENSE, WELL ESTABLISHED LAWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR AND RE-SODDING OF ALL ERODED, SUNKEN OR BARE SPOTS (LARGER THAN 12"X12") UNTIL CERTIFICATION OF ACCEPTABILITY BY THE OWNER'S REPRESENTATIVE. REPAIRED SODDING SHALL BE ACCOMPLISHED AS IN THE ORIGINAL WORK (INCLUDING REGRADING IF NECESSARY).
- B. CONTRACTOR RESPONSIBLE FOR ESTABLISHING AND MAINTAINING SOD/LAWN UNTIL ACCEPTANCE BY THE OWNER'S REPRESENTATIVE. PRIOR TO AND UPON ACCEPTANCE, CONTRACTOR TO PROVIDE WATERING/IRRIGATION SCHEDULE TO OWNER. OBSERVE ALL APPLICABLE WATERING RESTRICTIONS AS SET FORTH BY THE PROPERTY'S JURISDICTIONAL

UPON COMPLETION OF ALL PLANTING WORK AND BEFORE FINAL ACCEPTANCE, THE CONTRACTOR SHALL REMOVE ALL MATERIAL, EQUIPMENT, AND DEBRIS RESULTING FROM HIS WORK. ALL PAVED AREAS SHALL BE BROOM-CLEANED AND THE SITE LEFT IN A NEAT AND ACCEPTABLE CONDITION AS APPROVED BY THE OWNER'S AUTHORIZED REPRESENTATIVE.

### R. PLANT MATERIAL MAINTENANCE

ALL PLANTS AND PLANTING INCLUDED UNDER THIS CONTRACT SHALL BE MAINTAINED BY WATERING, CULTIVATING. SPRAYING, AND ALL OTHER OPERATIONS (SUCH AS RE-STAKING OR REPAIRING GUY SUPPORTS) NECESSARY TO INSURE A HEALTHY PLANT CONDITION BY THE CONTRACTOR UNTIL CERTIFICATION OF ACCEPTABILITY BY THE OWNER'S REPRESENTATIVE. MAINTENANCE AFTER THE CERTIFICATION OF ACCEPTABILITY SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS IN THIS SECTION. CONTRACTORS ARE REQUESTED TO PROVIDE A BID ESTIMATE TO COVER LANDSCAPE AND IRRIGATION MAINTENANCE FOR A PERIOD OF 90 CALENDAR DAYS COMMENCING AFTER ACCEPTANCE.

### S. MAINTENANCE (ALTERNATE BID ITEM)

CONTRACTORS ARE REQUESTED TO PROVIDE A BID ESTIMATE FOR MAINTENANCE FOLLOWING THE INITIAL 90-DAY MAINTENANCE PERIOD ON A COST-PER-MONTH BASIS.

### T. FINAL INSPECTION AND ACCEPTANCE OF WORK

FINAL INSPECTION AT THE END OF THE WARRANTY PERIOD SHALL BE ON PLANTING, CONSTRUCTION AND ALL OTHER INCIDENTAL WORK PERTAINING TO THIS CONTRACT. ANY REPLACEMENT AT THIS TIME SHALL BE SUBJECT TO THE SAME ONE (1) YEAR WARRANTY (OR AS SPECIFIED BY THE LANDSCAPE ARCHITECT OR OWNER IN WRITING) BEGINNING WITH THE TIME OF REPLACEMENT AND ENDING WITH THE SAME INSPECTION AND ACCEPTANCE HEREIN

### U. WARRANTY

- 1. THE LIFE AND SATISFACTORY CONDITION OF ALL PLANT MATERIAL INSTALLED BY THE LANDSCAPE CONTRACTOR SHALL BE WARRANTED BY THE CONTRACTOR FOR A MINIMUM OF ONE (1) CALENDAR YEAR COMMENCING AT THE TIME OF CERTIFICATION OF ACCEPTABILITY BY THE OWNER'S REPRESENTATIVE.
- 2. REPLACEMENT: ANY PLANT NOT FOUND IN A HEALTHY GROWING CONDITION AT THE END OF THE WARRANTY PERIOD SHALL BE REMOVED FROM THE SITE AND REPLACED AS SOON AS WEATHER CONDITIONS PERMIT. ALL REPLACEMENTS SHALL BE PLANTS OF THE SAME KIND AND SIZE AS SPECIFIED IN THE PLANT LIST. THEY SHALL BE FURNISHED PLANTED AND MULCHED AS SPECIFIED UNDER "PLANTING", AT NO ADDITIONAL COST TO THE OWNER.
- 3. IN THE EVENT THE OWNER DOES NOT CONTRACT WITH THE CONTRACTOR FOR LANDSCAPE (AND IRRIGATION) MAINTENANCE. THE CONTRACTOR IS ENCOURAGED TO VISIT THE PROJECT SITE PERIODICALLY DURING THE ONE YEAR WARRANTY PERIOD TO EVALUATE MAINTENANCE PROCEDURES BEING PERFORMED BY THE OWNER, AND SHALL NOTIFY THE OWNER IN WRITING OF MAINTENANCE PROCEDURES OR CONDITIONS WHICH THREATEN VIGOROUS AND HEALTHY PLANT GROWTH. IT IS SUGGESTED SUCH SITE VISITS SHALL BE CONDUCTED A MINIMUN OF ONCE PER MONTH FOR A PERIOD OF TWELVE (12) MONTHS FROM THE DATE OF ACCEPTANCE.

0 7



GR

Ś Ë Ш  $\geq$ <u>D</u>

Call before you dig. CITY OF PORT ST. LUCIE PROJECT 7

Know what's below.

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED ON THIS PROJECT. ONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE.

ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF

988 (NAVD '88). SUBTRACT 1.47' FROM NGVD '29 ELEVATION TO GET THE NAVD '88 ELEVATION

PSLUSD PROJECT # 5436

SHEET NUMBER L-151

# VALVE SCHEDULE

NUMBER	MODEL	SIZE	TYPE	<u>GPM</u>	<u>HEADS</u>	PIPE	DESIGN PSI	FRICTION LOSS	VALVE LOSS	PSI @ POC	PRECIP
C1	RAIN BIRD XCZF-100-PRF	1"	AREA FOR DRIPLINE	7.95	1,484 L.F.	22.2	20	0.22	9.24	44.7	0.24 in/h
C2	RAIN BIRD PEB	1"	BUBBLER	23	24	443.3	20	2.57	3.71	44.2	3.4 in/h
C3	RAIN BIRD PEB	1"	SHRUB SPRAY	25.22	24	396.8	30	1.36	4.31	54.3	0.9 in/h
C4	RAIN BIRD PEB	1"	SHRUB SPRAY	31.78	25	362.1	30	1.59	6.38	58.4	1.31 in/h
C5	RAIN BIRD XCZF-100-PRF	1"	AREA FOR DRIPLINE	6.13	1,226 L.F.	234.8	20	0.12	4.83	40.2	0.24 in/h
C6	RAIN BIRD PEB	1"	SHRUB SPRAY	9.06	11	154.1	30	0.62	1.78	47.9	1.55 in/h
C7	RAIN BIRD PEB	1"	BUBBLER	29.64	21	515.6	20	2.21	5.5	48.0	0.24 in/h
C8	RAIN BIRD PEB	1-1/2"	SHRUB SPRAY	34.22	14	190.8	30	0.57	3.56	55.9	1.3 in/h
C9	RAIN BIRD XCZF-100-PRF	1"	AREA FOR DRIPLINE	7.83	1,566 L.F.	32.2	20	0.22	8.95		0.24 in/h
C10	RAIN BIRD PEB	1-1/2"	SHRUB SPRAY	34.77	20	294.9	30	0.9	3.55		1.54 in/h
C11	RAIN BIRD PEB	1"	SHRUB SPRAY	34.72	24	301.1	30	0.85	7.68	56.5	1.57 in/h
C12	RAIN BIRD PEB	1"	SHRUB SPRAY	19.94	28	509.3	30	2.36	2.89	51.6	1.62 in/h
C13	RAIN BIRD PEB	1"	BUBBLER	24	24	625.1	20	2.98	3.98	43.7	3.4 in/h
C14	RAIN BIRD XCZF-100-PRF	1"	AREA FOR DRIPLINE	2.61	522.2 L.F.	23.6	20	0.02	0.3	35.3	0.24 in/h
C15	RAIN BIRD PEB	1"	SHRUB SPRAY	14.06	18	171.7	30	0.15	2.25	48.0	1.5 in/h
C16	RAIN BIRD PEB	1"	SHRUB SPRAY	19.5	16	189.0	30	0.49	2.85	49.9	1.62 in/h
C17	RAIN RIRD PER	1"	SHRUR SPRAY	11 75	a	116.2	30	0.17	1 00	48	0.98 in/h

IRRIGATION SCHEDULE								
SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	QTY	PSI					
<b>3 3 3 Q</b> T H F	RAIN BIRD 1806-SAM-PRS-U U8 SERIES SHRUB SPRAY, 6IN. POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL. 1/2IN. NPT FEMALE THREADED INLET. WITH SEAL-A-MATIC CHECK VALVE, AND PRESSURE REGULATING DEVICE.	4	30					
<b>© © © O O</b>	RAIN BIRD 1806-SAM-PRS-U U10 SERIES SHRUB SPRAY, 6IN. POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL. 1/2IN. NPT FEMALE THREADED INLET. WITH SEAL-A-MATIC CHECK VALVE, AND PRESSURE REGULATING DEVICE.	9	30					
	RAIN BIRD 1806-SAM-PRS-U U12 SERIES SHRUB SPRAY, 6IN. POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL. 1/2IN. NPT FEMALE THREADED INLET. WITH SEAL-A-MATIC CHECK VALVE, AND PRESSURE REGULATING DEVICE.	74	30					
	RAIN BIRD 1806-SAM-PRS-U U15 SERIES SHRUB SPRAY, 6IN. POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL. 1/2IN. NPT FEMALE THREADED INLET. WITH SEAL-A-MATIC CHECK VALVE, AND PRESSURE REGULATING DEVICE.	39	30					
3 08HE-VAN 2 12HE-VAN 10 10HE-VAN 5 15HE-VAN	RAIN BIRD 1806-SAM-PRS-U HE-VAN SERIES SHRUB SPRAY, 6IN. POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL. 1/2IN. NPT FEMALE THREADED INLET. WITH SEAL-A-MATIC CHECK VALVE, AND PRESSURE REGULATING DEVICE.	36	30					
0 10 10 00 Q T H F	RAIN BIRD 1812-SAM-PRS-U U10 SERIES SHRUB SPRAY, 12IN. POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL. 1/2IN. NPT FEMALE THREADED INLET. WITH SEAL-A-MATIC CHECK VALVE, AND PRESSURE REGULATING DEVICE.	22	30					
12 12 12 12 12 12 12 12 12 12 12 12 12 1	RAIN BIRD 1812-SAM-PRS-U U12 SERIES SHRUB SPRAY, 12IN. POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL. 1/2IN. NPT FEMALE THREADED INLET. WITH SEAL-A-MATIC CHECK VALVE, AND PRESSURE REGULATING DEVICE.	1	30					
8 08HE-VAN 12 12HE-VAN 10 10HE-VAN 15 15HE-VAN	RAIN BIRD 1812-SAM-PRS-U HE-VAN SERIES SHRUB SPRAY, 12IN. POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL. 1/2IN. NPT FEMALE THREADED INLET. WITH SEAL-A-MATIC CHECK VALVE, AND PRESSURE REGULATING DEVICE.	4	30					
▲ 回 △ □ 1401 1402 1404 1408	RAIN BIRD 1800-1400 FLOOD FIXED FLOW RATE 0.25 GPM - 2.0 GPM, FULL CIRCLE BUBBLER, 1/2IN. FIPT.	69	20					
SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	QTY						
	RAIN BIRD XCZF-100-PRF MEDIUM FLOW DRIP CONTROL KIT. 1IN. DV VALVE WITH 1IN. PRESSURE REGULATING FILTER AT , AND MDCF FITTING. 3 GPM-15 GPM.	4						
	PIPE TRANSITION POINT IN DRIP BOX PIPE TRANSITION POINT FROM PVC LATERAL TO DRIP TUBING WITH RISER IN 6IN. DRIP BOX.	9						
	AREA TO RECEIVE DRIPLINE RAIN BIRD XFS-06-24 XFS SUB-SURFACE PRESSURE COMPENSATING DRIPLINE W/COPPER SHIELD TECHNOLOGY. 0.6 GPH EMITTERS AT 24" O.C. LATERALS SPACED AT 24" APART, WITH EMITTERS OFFSET FOR TRIANGULAR PATTERN. UV RESISTANT. SPECIFY XF INSERT FITTINGS.	4,798 L.F.						
<u>SYMBOL</u>	MANUFACTURER/MODEL/DESCRIPTION	<u>QTY</u>						
	RAIN BIRD PEB 1IN., 1-1/2IN., 2IN. PLASTIC INDUSTRIAL VALVES. LOW FLOW OPERATING CAPABILITY, GLOBE CONFIGURATION.	13						
MV1	RAIN BIRD PESB 1-1/2"  1IN., 1-1/2IN., 2IN. PLASTIC INDUSTRIAL MASTER VALVES. LOW FLOW OPERATING CAPABILITY, GLOBE CONFIGURATION. WITH SCRUBBER TECHNOLOGY FOR RELIABLE PERFORMANCE IN DIRTY WATER IRRIGATION APPLICATIONS.	1						
BF	FEBCO 825YA 1-1/2" REDUCED PRESSURE BACKFLOW PREVENTER	1						
C1	RAIN BIRD ESPLXME2P W/ (2) ESPLXMSM12 36 STATION, TRADITIONALLY-WIRED , PRO SMART, COMMERCIAL CONTROLLER. (1) ESPLXME2P 12-STATION, PRO SMART, (MODULE INCLUDED) INDOOR/OUTDOOR, PLASTIC WALL-MOUNT ENCLOSURE W/ (2) ESPLXMSM12 - 12-STATION EXPANSION MODULES.	1						
RS	RAIN BIRD RSD-BEX RAIN SENSOR, WITH METAL LATCHING BRACKET, EXTENSION WIRE.	1						
	IRRIGATION LATERAL LINE: PVC CLASS 200 SDR 21	4,583 L.F.						
	IRRIGATION MAINLINE: PVC SCHEDULE 40	1,097 L.F.						
======	PIPE SLEEVE: PVC CLASS 200 TYPICAL PIPE SLEEVE FOR IRRIGATION PIPE. PIPE SLEEVE SIZE SHALL ALLOW FOR IRRIGATION PIPING AND THEIR RELATED COUPLINGS TO EASILY SLIDE THROUGH SLEEVING MATERIAL. EXTEND SLEEVES 18 INCHES BEYOND EDGES OF PAVING OR CONSTRUCTION.	519.3 L.F.						


## **GENERAL NOTES:**

1. A MINIMUM OF 5' HORIZONTAL AND 18" VERTICAL SEPARATION SHALL BE MAINTAINED FROM ALL EXISTING PSLUSD UTILITIES, INCLUDING WATER METERS AND SERVICES

Valve Callout

# ◆ \ # ◆ Valve Flow

---- Valve Number



GRAPHIC SCALE IN FEET

© 202 24TH

Know what's below.

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED ON THIS PROJECT.

CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE.

ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF

1988 (NAVD '88). SUBTRACT 1.47' FROM NGVD '29 ELEVATION TO GET THE NAVD '88 ELEVATION

Call before you dig.

CITY OF PORT ST. LUCIE PROJECT 7


PSLUSD PROJECT#

5436

P23-189

SHEET NUMBER

L-200



CITY OF PORT ST. LUCIE PROJECT P23-189 PSLUSD PROJECT#

ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF

1988 (NAVD '88). SUBTRACT 1.47' FROM NGVD '29 ELEVATION TO GET THE NAVD '88 ELEVATION

5436

SHEET NUMBER L-250

ORNER OF VILI & MARSHALL F

 $\geq$ 

RIG

0 24

## PART I: GENERAL

- A. THE WORK COVERED BY THIS SPECIFICATION SHALL INCLUDE THE FURNISHING OF ALL LABOR, MATERIALS, TOOLS AND EQUIPMENT NECESSARY TO PERFORM AND COMPLETE THE INSTALLATION OF AN AUTOMATIC IRRIGATION SYSTEM AS SPECIFIED HEREIN AND AS SHOWN ON THE DRAWINGS AND ANY INCIDENTAL WORK NOT SHOWN OR SPECIFIED WHICH CAN REASONABLY BE DETERMINED TO BE PART OF THE WORK AND NECESSARY TO PROVIDE A COMPLETE AND FUNCTIONAL SYSTEM.
- B. THE WORK COVERED BY THIS SPECIFICATION ALSO INCLUDES ALL PERMITS, FEDERAL, STATE AND LOCAL TAXES AND ALL OTHER COSTS, BOTH FORESEEABLE AND UNFORESEEABLE AT THE TIME OF CONSTRUCTION.
- C. NO DEVIATION FROM THESE SPECIFICATIONS, THE ACCOMPANYING DRAWINGS, OR AGREEMENT IS AUTHORIZED OR SHALL BE MADE WITHOUT PRIOR WRITTEN AUTHORIZATION SIGNED BY THE OWNER OR HIS DULY APPOINTED REPRESENTATIVE.
- B. COORDINATION: COORDINATE AND COOPERATE WITH OTHER CONTRACTORS TO ENABLE THE WORK TO PROCEED AS RAPIDLY AND EFFICIENTLY AS POSSIBLE.
- C. INSPECTION OF SITE: THE CONTRACTOR SHALL ACQUAINT HIMSELF WITH ALL SITE CONDITIONS, INCLUDING UNDERGROUND UTILITIES BEFORE CONSTRUCTION IS TO BEGIN. CONTRACTOR SHALL COORDINATE THE VICINITY OR THOSE SCHEDULED TO DO UNDERGROUND WORK IN THE VICINITY. CONTRACTOR IS RESPONSIBLE FOR MINOR ADJUSTMENTS IN THE LAYOUT OF THE WORK TO ACCOMMODATE EXISTING
- D. PROTECTION OF EXISTING PLANTS AND SITE CONDITIONS: THE CONTRACTOR SHALL TAKE NECESSARY PRECAUTIONS TO PROTECT SITE CONDITIONS TO REMAIN. SHOULD DAMAGES BE INCURRED, THIS CONTRACTOR SHALL REPAIR THE DAMAGE TO ITS ORIGINAL CONDITION AT HIS OWN EXPENSE. ANY DISRUPTION, DESTRUCTION, OR DISTURBANCE OF ANY EXISTING PLANT, TREE, SHRUB, OR TURF, OR ANY STRUCTURE SHALL BE COMPLETELY RESTORED TO THE SATISFACTION OF THE OWNER AND HIS REPRESENTATIVES, SOLELY AT THE CONTRACTOR'S EXPENSE.
- PROTECTION OF WORK AND PROPERTY: THE CONTRACTOR SHALL BE LIABLE FOR AND SHALL TAKE THE
- ROADS, GROUNDS, LANDSCAPING OR STRUCTURE OF ANY KIND (INCLUDING WITHOUT LIMITATION, DAMAGE FROM LEAKS IN THE PIPING SYSTEM BEING INSTALLED OR HAVING BEEN INSTALLED BY CONTRACTOR) DAMAGED BY THE CONTRACTOR, OR BY HIS AGENTS, EMPLOYEES, OR SUBCONTRACTORS OR REPAIRED BY CONTRACTOR AT HIS OWN EXPENSE IN A MANNER SATISFACTORY TO OWNER, WHICH REPAIR OR REPLACEMENT SHALL BE A CONDITION PRECEDENT TO OWNER'S OBLIGATION TO MAKE FINAL PAYMENT UNDER THE CONTRACT.
- 2. CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR DAMAGE TO ANY WORK COVERED BY THESE SPECIFICATIONS BEFORE FINAL ACCEPTANCE OF THE WORK. HE SHALL SECURELY COVER ALL OPENINGS INTO THE SYSTEMS AND COVER ALL APPARATUS, EQUIPMENT AND APPLIANCES, BOTH BEFORE AND AFTER BEING SET IN PLACE TO PREVENT OBSTRUCTIONS ON THE PIPES AND THE BREAKAGE, MISUSE OR DISFIGUREMENT
- 3. ALL TRENCHING OR OTHER WORK UNDER THE LEAF CANOPY OF ANY AND ALL TREES SHALL BE DONE BY HAND OR BY OTHER METHODS SO THAT NO BRANCHES ARE DAMAGED IN ANY WAY. BUILDINGS, WALKS, WALLS, AND OTHER PROPERTY SHALL BE PROTECTED FROM DAMAGE. OPEN DITCHES LEFT EXPOSED SHALL BE FLAGGED AND BARRICADED BY THE CONTRACTOR BY APPROVED MEANS. THE CONTRACTOR SHALL RESTORE DISTURBED AREAS TO THEIR ORIGINAL CONDITION.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REQUESTING THE PROPER UTILITY COMPANY TO STAKE THE EXACT LOCATION OF ANY UNDERGROUND LINES INCLUDING BUT NOT LIMITED TO ELECTRIC, GAS, TELEPHONE SERVICE, WATER, AND CABLE. THE CONTRACTOR SHALL TAKE WHATEVER PRECAUTIONS ARE NECESSARY TO PROTECT THESE UNDERGROUND LINES FROM DAMAGE. IN THE EVENT DAMAGE DOES OCCUR, ALL DAMAGE SHALL BE COMPLETELY REPAIRED TO ITS ORIGINAL CONDITION, AT NO ADDITIONAL COST TO THE OWNER.
- 5. THE CONTRACTOR SHALL REQUEST THE OWNER, IN WRITING, TO LOCATE ANY PRIVATE UTILITIES (I.E., ELECTRICAL SERVICE TO OUTSIDE LIGHTING) BEFORE PROCEEDING WITH ANY EXCAVATION. IF, AFTER SUCH REQUESTS AND NECESSARY STAKING, PRIVATE UTILITIES WHICH WERE NOT STAKED ARE ENCOUNTERED AND DAMAGED BY THE CONTRACTOR, THEY SHALL BE REPAIRED BY THE OWNER AT NO COST TO THE CONTRACTOR. IF THE CONTRACTOR DAMAGES STAKED OR LOCATED UTILITIES, THEY SHALL BE REPAIRED AT
- F. CODES AND INSPECTIONS: THE ENTIRE INSTALLATION SHALL COMPLY FULLY WITH ALL LOCAL AND STATE LAWS AND ORDINANCES AND WITH ALL ESTABLISHED CODES ARRANGE FOR ALL NECESSARY INSPECTIONS AND SHALL PAY ALL FEES AND EXPENSES IN CONNECTION WITH SAME, AS PART OF THE WORK UNDER THIS CONTRACT. UPON COMPLETION OF THE WORK. HE SHALL FURNISH TO THE "OWNER" ALL INSPECTION CERTIFICATES
- G. THE CONTRACTOR SHALL KEEP ON HIS WORK, DURING ITS PROGRESS, A COMPETENT SUPERINTENDENT AND ANY NECESSARY ASSISTANTS, ALL SATISFACTORY TO THE OWNER, OR OWNER'S REPRESENTATIVE.
- HIM SHALL BE AS BINDING AS IF GIVEN TO THE CONTRACTOR.
- THE OWNER'S LANDSCAPE ARCHITECT OR DESIGNATED INDIVIDUAL SHALL HAVE FULL AUTHORITY TO APPROVE OR REJECT WORK PERFORMED BY THE CONTRACTOR. THE OWNER'S AUTHORIZED REPRESENTATIVE SHALL ALSO HAVE FULL AUTHORITY TO MAKE FIELD CHANGES THAT ARE DEEMED NECESSARY.
- J. FINAL ACCEPTANCE: FINAL ACCEPTANCE OF THE WORK MAY BE OBTAINED FROM THE OWNER UPON THE ADJUSTMENTS TO ELIMINATE ANY DEFICIENCIES WHICH MAY LATER BE DISCOVERED.
- K. GUARANTEE: ALL WORK SHALL BE GUARANTEED FOR ONE YEAR FROM DATE OF FINAL ACCEPTANCE AGAINST IF REQUIRED, SHALL BE DONE PROMPTLY AT NO COST TO THE OWNER.
  - LEAKS OR WORKMANSHIP, TO THE SATISFACTION OF THE OWNER. THE CONTRACTOR SHALL NOT BE TERMINATION DATE, NAME AND LICENSE NUMBER OF CONTRACTOR PROVIDING GUARANTEE, ADDRESS, AND TELEPHONE NUMBER. IT SHALL BE SIGNED BY THE CHIEF EXECUTIVE OF THE CONTRACTOR OF HIS LIABILITY UNDER THE GUARANTEE. SUCH WARRANTIES SHALL ONLY SUPPLEMENT THE GUARANTEE.
  - 2. IF, WITHIN TEN (10) DAYS AFTER MAILING OF WRITTEN NOTICE BY THE OWNER TO THE CONTRACTOR REQUESTING REPAIRS OR REPLACEMENT RESULTING FROM A BREACH OF WARRANTY, THE CONTRACTOR SHALL NEGLECT TO MAKE OR UNDERTAKE WITH DUE DILIGENCE TO MAKE THE SAME. THE OWNER MAY MAKE SUCH REPAIRS AT THE CONTRACTOR'S EXPENSE; PROVIDED, HOWEVER, THAT IN THE CASE OF REPAIRS OR REPLACEMENT MAY BE MADE WITHOUT NOTICE BEING SENT TO THE CONTRACTOR, AND CONTRACTOR SHALL PAY THE COST THEREOF.
- THE CONTRACTOR SHALL PROVIDE FULL, 100% IRRIGATION COVERAGE IN ALL AREAS DESIGNED WITH
- CONTRACTOR, THE OWNER OR LANDSCAPE ARCHITECT MAY VISIT THE SITE TO OBSERVE WORK UNDERWAY. UPON REQUEST. THE CONTRACTOR SHALL BE REQUIRED TO UNCOVER SPECIFIED WORK AS DIRECTED BY THE OWNER OR MATERIAL, WORKMANSHIP OR METHOD OF INSTALLATION NOT MEET THE STANDARDS SPECIFIED HEREIN, THE CONTRACTOR SHALL REPLACE THE WORK AT HIS OWN EXPENSE
- N. WORKMANSHIP: ALL WORK SHALL BE INSTALLED BY QUALIFIED, SKILLED PERSONNEL, PROFICIENT IN THE TRADES REQUIRED, IN A NEAT, ORDERLY, AND RESPONSIBLE MANNER WITH RECOGNIZED STANDARDS OF WORKMANSHIP. THE CONTRACTOR SHALL HAVE HAD CONSIDERABLE EXPERIENCE AND DEMONSTRATED ABILITY IN THE INSTALLATION OF SPRINKLER IRRIGATION SYSTEMS OF THIS TYPE.

- ALL MATERIALS SHALL BE THOSE SPECIFIED AND/OR APPROVED BY THE LANDSCAPE ARCHITECT.
- A. PRODUCT DATA: AFTER THE AWARD OF THE CONTRACT AND PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL SUBMIT FOR APPROVAL BY THE OWNER AND LANDSCAPE ARCHITECT, TWO COPIES OF THE COMPLETE LIST OF MATERIALS, MANUFACTURER'S TECHNICAL DATA, AND INSTALLATION INSTRUCTIONS WHICH HE
- ARCHITECT.
- C. RECORD DRAWINGS: THE CONTRACTOR SHALL RECORD ON REPRODUCIBLES, ALL CHANGES THAT MAY BE MADE DURING ACTUAL INSTALLATION OF THE SYSTEM. PROVIDE CONTROLLER SEQUENCING AND CONTROL VALVE LOCATIONS
- 1. IMMEDIATELY UPON INSTALLATION OF ANY PIPING, VALVES, WIRING, SPRINKLERS, ETC., IN LOCATIONS OTHER THAN SHOWN ON THE ORIGINAL DRAWINGS OR OF SIZES OTHER THAN INDICATED, THE CONTRACTOR SHALL CLEARLY INDICATE SUCH CHANGES ON A SET OF BLUELINE PRINTS. RECORDS SHALL BE
- MADE ON A DAILY BASIS. ALL RECORDS SHALL BE NEAT AND SUBJECT TO THE APPROVAL OF THE OWNER. 2. THE CONTRACTOR SHALL ALSO INDICATE ON THE RECORD PRINTS THE LOCATION OF ALL WIRE SPLICES,

- ORIGINAL OR DUE TO REPAIR, THAT ARE INSTALLED UNDERGROUND IN A LOCATION OTHER THAN THE CONTROLLER PEDESTAL, REMOTE CONTROL VALVE BOX, POWER SOURCE OR CONNECTION TO A VALVE-IN-HEAD SPRINKLER.
- 3. THESE DRAWINGS SHALL ALSO SERVE AS WORK PROGRESS SHEETS. THE CONTRACTOR SHALL MAKE NEAT AND LEGIBLE NOTATIONS THEREON DAILY AS THE WORK PROCEEDS, SHOWING THE WORK AS ACTUALLY INSTALLED. THESE DRAWINGS SHALL BE AVAILABLE AT ALL TIMES FOR REVIEW AND SHALL BE KEPT IN A LOCATION DESIGNATED BY THE OWNER'S REPRESENTATIVE.
- 4. PROGRESS PAYMENT REQUEST AND RECORD DRAWING INFORMATION MUST BE APPROVED BY LANDSCAPE ARCHITECT BEFORE PAYMENT IS MADE.
- 5. IF IN THE OPINION OF THE OWNER OR HIS REPRESENTATIVE, THE RECORD DRAWING INFORMATION IS NOT BEING PROPERLY OR PROMPTLY RECORDED, CONSTRUCTION PAYMENT MAY BE STOPPED UNTIL THE PROPER INFORMATION HAS BEEN RECORDED AND SUBMITTED.
- 6. BEFORE THE DATE OF THE FINAL SITE OBSERVATION AND APPROVAL, THE CONTRACTOR SHALL DELIVER ONE SET (COPIES) OF REPRODUCIBLE RECORD DRAWING PLANS AND NOTES TO THE LANDSCAPE ARCHITECT. RECORD DRAWING INFORMATION SHALL BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO
- D. OPERATIONS AND MAINTENANCE MANUALS: THE CONTRACTOR SHALL PREPARE AND DELIVER TO THE OWNER, OR HIS DESIGNATED REPRESENTATIVE WITHIN TEN (10) CALENDAR DAYS PRIOR TO COMPLETION OF
- CONSTRUCTION, A HARD COVER BINDER WITH THREE RINGS CONTAINING THE FOLLOWING INFORMATION: 1. INDEX SHEET STATING THE CONTRACTOR'S ADDRESS AND BUSINESS TELEPHONE NUMBER, LIST OF EQUIPMENT WITH NAME(S) AND ADDRESS(ES) OF LOCAL MANUFACTURER'S REPRESENTATIVE(S).
- 2. CATALOG AND PARTS SHEETS ON EVERY MATERIAL AND EQUIPMENT INSTALLED UNDER THIS CONTRACT. 3. COMPLETE OPERATING AND MAINTENANCE INSTRUCTION ON ALL MAJOR EQUIPMENT. INCLUDE INITIAL CONTROLLER SCHEDULE AND RECOMMENDED SCHEDULE AFTER ESTABLISHMENT PERIOD. 4. DEMONSTRATE TO AND PROVIDE THE OWNER'S MAINTENANCE PERSONNEL WITH INSTRUCTIONS FOR

### REPRESENTATIVE AT THE CONCLUSION OF THE PROJECT THAT THIS SERVICE HAS BEEN RENDERED. 1.04 EXPLANATION OF DRAWINGS

A. DUE TO THE SCALE OF THE DRAWINGS, IT IS NOT POSSIBLE TO INDICATE ALL OFFSETS, FITTINGS AND SLEEVES WHICH MAY BE REQUIRED. THE CONTRACTOR SHALL CAREFULLY INVESTIGATE THE STRUCTURAL AND FINISHED CONDITIONS AFFECTING ALL OF THE WORK AND PLAN HIS WORK ACCORDINGLY, FURNISHING SUCH OFFSETS, FITTINGS AND SLEEVES AS MAY BE REQUIRED TO MEET SUCH CONDITIONS.

MAJOR EQUIPMENT AND SHOW EVIDENCE IN WRITING TO THE OWNER, OR HIS DESIGNATED

- B. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATIVE OF THE WORK TO BE INSTALLED. THE WORK SHALL BE INSTALLED IN SUCH A MANNER AS TO AVOID CONFLICTS BETWEEN IRRIGATION SYSTEMS, PLANTING AND ARCHITECTURAL FEATURES. DEVIATIONS SHALL BE BROUGHT TO THE LANDSCAPE ARCHITECTS
- C. ALL WORK CALLED FOR A ON THE DRAWINGS BY NOTES OR DETAILS SHALL BE FURNISHED AND INSTALLED WHETHER OR NOT SPECIFICALLY MENTIONED IN THE SPECIFICATIONS.
- THE CONTRACTOR SHALL NOT WILLFULLY INSTALL THE IRRIGATION SYSTEM AS SHOWN ON THE DRAWINGS WHEN IT IS OBVIOUS IN THE FIELD THAT OBSTRUCTIONS, GRADE DIFFERENCES OR DISCREPANCIES IN AREA DIMENSIONS EXIST THAT MIGHT NOT HAVE BEEN KNOWN IN ENGINEERING. SUCH OBSTRUCTIONS OR DIFFERENCES SHOULD BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT. IN THE EVENT THAT NOTIFICATION IS NOT PERFORMED, THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ANY REVISION
- E. IF, IN THE OPINION OF THE LANDSCAPE ARCHITECT, THE LABOR FURNISHED BY THE CONTRACTOR IS INCOMPETENT, UNSKILLED, OR UNRELIABLE, HIS EQUIPMENT INADEQUATE, IMPROPER OR UNSAFE, OR IF THE CONTRACTOR SHALL FAIL TO CONTINUOUSLY AND DILIGENTLY EXECUTE THE CONSTRUCTION, THE LANDSCAPE ARCHITECT OR OWNER SHALL, IN WRITING, INSTRUCT THE CONTRACTOR TO REMOVE ALL SUCH CAUSES OF NONCOMPLIANCE AND THE CONTRACTOR SHALL PROMPTLY COMPLY.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR FULL AND COMPLETE COVERAGE OF ALL IRRIGATION AREAS. THE LANDSCAPE ARCHITECT SHALL BE NOTIFIED OF ANY NECESSARY ADJUSTMENTS AT NO ADDITIONAL COST TO THE OWNER. ANY REVISIONS TO THE IRRIGATION SYSTEM MUST BE SUBMITTED AND ANSWERED IN WRITTEN FORM, ALONG WITH ANY CHANGE IN CONTRACT PRICE. LAYOUT MAY BE MODIFIED, IF NECESSARY TO OBTAIN COVERAGE. SPACING NOT TO EXCEED 60% OF THE DIAMETER.

### PART II: PRODUCTS

A. MATERIAL AND EQUIPMENT SHALL BE SUPPLIED BY THE CONTRACTOR. NO SUBSTITUTIONS SHALL BE ALLOWED WITHOUT THE PRIOR WRITTEN APPROVAL OF THE OWNER/LANDSCAPE ARCHITECT. THE CONTRACTOR SHALL INSPECT ALL MATERIALS AND FOLIPMENT PRIOR TO INSTALLATION, AND DEFECTIVE MATERIALS SHALL BE REPLACED WITH THE PROPER MATERIALS AND EQUIPMENT. THOSE ITEMS USED IN THE INSTALLATION FOUND TO BE DEFECTIVE. IMPROPERLY INSTALLED OR NOT AS SPECIFIED. SHALL BE REMOVED AND THE PROPER MATERIALS AND EQUIPMENT INSTALLED IN THE PROPER MANNER, AS INTERPRETED BY THE EQUIPMENT FROM THE SITE.

- A. GENERAL PROVISIONS: ALL MATERIALS THROUGHOUT THE SYSTEM SHALL BE NEW AND IN PERFECT CONDITION UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT.
- B. POLYVINYL CHLORIDE PIPE (PVC): (WHERE INDICATED ON PLAN, USE NON-POTABLE PURPLE PIPING.)
- 1. LATERALS: PVC SHALL CONFORM TO THE REQUIREMENTS OF ASTM DESIGNATION D 2241, CLASS 1120 OR 1220. ALL LATERAL PIPING LESS THAN 3" IN DIAMETER SHALL BE CLASS 200 SDR-21. 2. MAIN LINE UNDER PRESSURE: PVC SHALL CONFORM TO THE REQUIREMENTS OF ASTM DESIGNATION D
- 2241, CLASS 1120 OR 1220, SCHEDULE 40 WITH BELLED END FOR SOLVENT WELD CONNECTION. 3. PIPE MARKINGS: ALL PVC PIPE SHALL BEAR THE FOLLOWING MARKINGS:
- a. MANUFACTURER'S NAME
- b. NOMINAL PIPE SIZE c. SCHEDULE OR CLASS
- d. PRESSURE RATING OF PSI
- e. NSF (NATIONAL SANITATION FOUNDATION) APPROVAL
- f. DATE OF EXTRUSION

## 2.03 PVC JOINTS

- A. JOINTS IN PVC PIPE SMALLER THAN 3" SHALL BE SOLVENT WELDED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE PIPE MANUFACTURER; THE SOLVENT CLEANER AND WELDING COMPOUND FURNISHED WITH THE PIPE.
- A. THREADED PVC CONNECTIONS SHALL BE MADE UP USING TEFLON TAPE ONLY.
- B. CONNECTION BETWEEN MAINLINE PIPE FITTINGS AND AUTOMATIC OR MANUAL CONTROL VALVES SHALL BE
- MADE USING SCHEDULE 80 THREADED FITTINGS AND NIPPLES. 2.05 SOLVENT CEMENT
- A. GENERAL: PROVIDE SOLVENT CEMENT AND PRIMER FOR PVC SOLVENT WELD PIPE AND FITTINGS RECOMMENDED BY THE MANUFACTURER. PIPE JOINTS FOR SOLVENT WELD PIPE TO BE BELLED END. PIPE JOINTS FOR GASKETED PIPE TO BE INTRICAL RING TYPE. INSERT GASKETS WILL NOT BE ACCEPTED.
- B. THRUST BLOCKS: MAIN LINE PIPING 3" OR GREATER IN DIAMETER SHALL HAVE THRUST BLOCKS SIZED AND PLACED IN ACCORDANCE WITH THE PIPE MANUFACTURER'S RECOMMENDATIONS OR, IN THE ABSENCE OF SPECIFIED RECOMMENDATIONS BY THE PIPE MANUFACTURER. 3000 PSI CONCRETE THRUSTS SHALL BE PROPERLY INSTALLED AT TEES, ELBOWS, 45'S, CROSSES, REDUCERS, PLUGS, CAPS AND VALVES.

### 2.06 PIPE AND WIRE SLEEVES A. SLEEVES TO BE INSTALLED:

2.04 THREADED CONNECTIONS

- 1. THE CONTRACTOR SHALL INSTALL IRRIGATION SYSTEM PIPE AND WIRE SLEEVES CONFORMING TO THE
- a. ALL PIPE SLEEVES SHALL EXTEND A MINIMUM OF 36" BEYOND THE EDGES OF PAVEMENT.
- b. ALL PIPE SLEEVES TO BE INSTALLED BENEATH FUTURE/EXISTING ROAD SURFACES SHALL BE PVC PIPE SCHEDULE 40 OR JACK AND BORE STEEL PIPE AS PER FDOT SPECIFICATIONS, AND AS SHOWN ON
- c. ALL IRRIGATION SYSTEM WIRES SHALL BE SLEEVED SEPARATELY FROM MAIN OR LATERAL LINES. d. ALL PIPE SLEEVES SHALL BE INSTALLED AT THE MINIMUM DEPTH SPECIFIED FOR MAIN LINES, LATERAL LINES, AND ELECTRIC WIRE.
- e. CONTRACTOR SHALL COORDINATE ALL PIPE SLEEVE LOCATIONS AND DEPTHS PRIOR TO INITIATING INSTALLATION OF THE IRRIGATION SYSTEM.
- 2.09 AUTOMATIC CONTROL VALVE A. THE AUTOMATIC REMOTE CONTROL VALVES SHALL BE AS SPECIFIED ON THE PLANS, OR APPROVED EQUAL. 2.10 GATE VALVES
- A. GATE VALVES FOR 3/4" THROUGH 2-1/2" SHALL BE OF BRASS OR BRONZE CONSTRUCTION, SOLID WEDGE, IPS THREADS, NON-RISING STEM WITH WHEEL OPERATING HANDLE, FOR A CONTINUOUS WORKING PRESSURE OF

- B. GATE VALVES FOR 3" AND LARGER: IRON BODY, BRASS OR BRONZE MOUNTED AWWA GATE VALVES, WITH A CLEAR WATERWAY EQUAL TO THE FULL NOMINAL DIAMETER OF THE VALVE, RUBBER GASKET FOR A
- A. FOR GATE VALVES, USE AMETEK #10-181-014 BOX WITH #10-181-015 LOCKING LID, OR AS PER THE DRAWINGS.
- C. FOR CONTROL WIRING SPLICES, USE AMETEK #10-181-014 BOX WITH #10-181-015 LOCKING LID, OR AS PER THE
- WIRING USED FOR CONNECTING THE ELECTRIC CONTROL VALVES TO THE CONTROLLERS SHALL BE TYPE UF, 600 VOLT, SINGLE STRAND, SOLID COPPER WITH PVC INSULATION 4/64" THICK. SIZE SHALL BE 14 GAUGE, RED FOR

- A. DRAINAGE BACKFILL: CLEANED GRAVEL OR CRUSHED STONE, GRADED FROM 1" MAXIMUM TO 3/4" MINIMUM.
- B. METALIZED UNDERGROUND TAPE: THE DETECTABLE, UNDERGROUND UTILITY MARKING TAPE SHALL CONSIST OF A MINIMUM: 5 MIL (0.005") OVERALL THICKNESS; FIVE-PLY COMPOSITION; ULTRA-HIGH MOLECULAR WEIGHT, 100% VIRGIN POLYETHYLENE: ACID. ALKALINE AND CORROSION RESISTANT: WITH NO LESS THAN 150 POUNDS OF TENSILE BREAK STRENGTH PER 6" WIDTH; COLOR-CODE IMPREGNATED WITH COLOR STABLE, LEAD-FREE, ORGANIC PIGMENTS SUITABLE FOR DIRECT BURIAL. TAPES UTILIZING REPROCESSED PLASTICS OR RESINS SHALL NOT BE ACCEPTABLE. THE DETECTABLE, UNDERGROUND UTILITY MARKING TAPE SHALL HAVE A 35 GAUGE (0.0035") SOLID ALUMINUM FOIL, CORE ENCAPSULATED WITHIN A 2.55 MIL (0.00255") POLYETHYLENE BACKING AND A 0.6 MIL (0.006") PET COVER COATING. THE LAMINATE ON EACH SIDE SHALL CONSIST OF A 0.75 MIL (0.00075") LAYER OF HOT LPDE, POLY-FUSING THE "SANDWICH" WITHOUT USE OF ADHESIVES.
- a. EACH STATION SHALL BE CAPABLE OF TIMING FROM ZERO (0) MINUTE TO 99 MINUTES PER
- b. EACH STATION SHALL BE CAPABLE OF OPERATING TWO (2) 7VA ELECTRIC VALVE-IN-HEAD
- d. THE STAND-ALONE CONTROLLER SHALL PROVIDE GLOBAL PERCENTAGE INCREASE/DECREASE
- e. ALL STATIONS SHALL BE ABLE TO BE TURNED ON/OFF MANUALLY BUY OPERATING TIMING
- MECHANISM OR BY MANUAL SWITCH AT STATION OUTPUT. f. THE STAND-ALONE CONTROLLER SHALL INCORPORATE AN INTEGRAL MOV SURGE PROTECTION INTO THE TERMINAL BLOCK FOR EACH OF ITS 24 VAC FIELD WIRE OUTPUTS. CONTROLLER POWER
- g. THE CONTROL PANEL SHALL PROVIDE CONTINUOUS DISPLAY TIME. IT SHALL HAVE SELECTION OF FUNCTION AND PRECISION VALUE ADJUSTMENT BY ROTARY DIAL INPUT.
- h. THE STAND-ALONE CONTROLLER SHALL BE UL LISTED AND FCC APPROVED. i.THE STAND-ALONE CONTROLLER SHALL HAVE 117 VAC, 60 HZ INPUT, 26.5 VAC, 60 HZ OUTPUT FOR
- j.THE STAND-ALONE CONTROLLER CABINET SHALL BE A LOCKABLE AND WEATHER-RESISTANT OUTDOOR
- k. THE CONTROLLER SHALL BE EQUIPPED WITH LIGHTENING PROTECTION, BY THE CONTRACTOR, ON BOTH THE PRIMARY (120V) AND EACH SECONDARY (24V) CIRCUIT. THE CONTROLLER CIRCUITS SHALL BE GROUNDED TO A COPPER CLAD GROUNDING ROD LOCATED AT EACH CONTROLLER.
- I. THE CONTROLLER SHALL BE EQUIPPED FOR A WATER CONSERVATION DEVICE. AS SPECIFIED.

## PART III: EXECUTION

A. THE CONTRACTOR SHALL EXAMINE THE AREAS AND CONDITIONS UNDER WHICH LANDSCAPE IRRIGATION SYSTEM IS TO BE INSTALLED AND NOTIFY THE LANDSCAPE ARCHITECT IN WRITING OF CONDITIONS DETRIMENTAL TO THE PROPER AND TIMELY COMPLETION OF THE WORK. THE CONTRACTOR SHALL PROCEED WITH THE WORK UNTIL UNSATISFACTORY CONDITIONS HAVE BEEN CORRECTED IN A MANNER ACCEPTABLE TO

## 3.02 PREPARATION

- A. THE CONTRACTOR SHALL PROVIDE SLEEVES TO ACCOMMODATE PIPING UNDER WALKS OR PAVING. THE WORK. CUTTING AND PATCHING OF PAVING AND CONCRETE WILL NOT BE PERMITTED. THE CONTRACTOR SHALL MAINTAIN ALL WARNING SIGNS, SHORING, BARRICADES, FLARES AND RED LANTERNS, AS REQUIRED BY ANY LOCAL CODES, ORDINANCES OR PERMITS.
- 3.03 TRENCHING AND BACKFILLING
- A. EXCAVATION: THE CONTRACTOR SHALL STAKE OUT THE LOCATION OF EACH RUN OF PIPE, SPRINKLER HEADS, SPRINKLER VALVES AND ISOLATION VALVES PRIOR TO TRENCHING. EXCAVATION SHALL BE OPEN VERTICAL CONSTRUCTION SUFFICIENTLY WIDE TO PROVIDE FREE WORKING SPACE AROUND THE WORK INSTALLED AND TO PROVIDE AMPLE SPACE OR BACKFILLING AND TAMPING. TRENCHES FOR PIPE SHALL BE CUT TO REQUIRED GRADE LINES, AND COMPACTED TO PROVIDE ACCURATE GRADE AND UNIFORM BEARING FOR THE FULL LENGTH OF THE LINE. THE BOTTOM OF THE TRENCHES SHALL BE FREE OF ROCK OR OTHER SHARP EDGED OBJECTS. MINIMUM COVER SHALL BE AS FOLLOWS:

18" AT TOP OF PIPE FROM FINISH GRADE PRESSURE MAINLINE 12" AT TOP OF PIPE FROM FINISH GRADE LATERAL PIPING (ROTOR) LATERAL PIPING (POP-UP) 12" AT TOP OF PIPE FROM FINISH GRADE

- B. MINIMUM CLEARANCES: ALL PIPELINES SHALL HAVE A MINIMUM CLEARANCE OF SIX INCHES FROM EACH OTHER AND FROM LINES OF OTHER CRAFTS. PARALLEL LINES SHALL NOT BE INSTALLED DIRECTLY OVER ONE ANOTHER. NO LATERAL LINE SHALL BE INSTALLED IN THE MAIN-LINE TRENCH
- A. PVC PIPE AND JOINTS: THE CONTRACTOR SHALL NOT INSTALL SOLVENT WILD PIPE WHEN AIR TEMPERATURE IS BELOW 40Ø F. INSTALLATION SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. 1. ONLY THE SOLVENT RECOMMENDED BY THE PIPE MANUFACTURER SHALL BE USED. ALL PVC PIPE AND
- FITTINGS SHALL BE INSTALLED AS OUTLINED AND INSTRUCTED BY THE PIPE MANUFACTURER, AND IT SHALL BE THE CONTRACTOR'S FULL RESPONSIBILITY TO MAKE ARRANGEMENTS WITH THE PIPE MANUFACTURER FOR ANY FIELD ASSISTANCE THAT MAY BE NECESSARY. THE CONTRACTOR SHALL ASSUME FULL

- INITIAL BACKFILL ON PVC LINES SHALL BE PULVERIZED NATIVE SOIL, FREE OF FOREIGN MATTER. WITHIN RADIUS OF 4" OF THE PIPE SHALL BE CLEAN SOIL OR SAND. PLANT LOCATIONS SHALL TAKE PRECEDENCE OVER SPRINKLER AND PIPE LOCATIONS. THE CONTRACTOR SHALL COORDINATE THE LOCATION OF TREES AND SHRUBS WITH THE ROUTING OF
- A. BACKFILL AND COMPACTION: THE CONTRACTOR SHALL LEAVE TRENCHES SLIGHTLY MOUNDED TO ALLOW FOR SETTLEMENT AFTER THE BACKFILLING IS COMPLETED. THE CONTRACTOR SHALL CLEAN THE SITE OF THE WORK CONTINUOUSLY OF EXCESS WASTE MATERIALS AS THE BACKFILLING PROGRESSES, AND LEAVE IN A NEAT CONDITION. NO TRENCHES SHALL BE LEFT OPEN FOR A PERIOD OF MORE THAN 48 HOURS. PROTECT OPEN
- 1. THE CONTRACTOR SHALL CAREFULLY BACKFILL EXCAVATED MATERIALS APPROVED FOR BACKFILLING, 1" IN SIZE. BACKFILL SHALL BE COMPACTED TO ORIGINAL DENSITY OF SURROUNDING SOIL WITHOUT DIPS, SUNKEN AREAS, OR IRREGULARITIES.
- 2. THE CONTRACTOR SHALL CONFORM TO DOT REQUIREMENTS FOR METHODS AND REQUIRED COMPACTION PERCENTAGES, FOR ROADS AND PAVING.
- 3. THE CONTRACTOR SHALL HAND PLACE THE FIRST 6" OF BACKFILL (OR TO TOP OF PIPE) AND HAVE IT WALKED
- 4. NO WHEEL ROLLING WILL BE ALLOWED. THE CONTRACTOR SHALL REMOVE ROCK OR DEBRIS EXTRACTED FROM BACKFILL MATERIALS AND DISPOSE OF OFFSITE. THE CONTRACTOR SHALL FILL ANY VOIDS LEFT IN

BACKFILL WITH APPROVED BACKFILL MATERIALS.

- B. EXISTING LAWNS: WHERE TRENCHING IS REQUIRED ACROSS EXISTING LAWNS. UNIFORMLY CUT STRIPS OF SOD 6" WIDER THAN TRENCH. THE CONTRACTOR SHALL REMOVE SOD IN ROLLS OF SUITABLE SIZE FOR HANDLING AND KEEP MOISTENED UNTIL REPLANTED. THE CONTRACTOR SHALL REPLANT SOD WITHIN 48 HOURS AFTER REMOVAL, ROLL AND WATER GENEROUSLY. THE CONTRACTOR SHALL RESOD ANY AREAS NOT IN HEALTHY CONDITION EQUAL TO ADJOINING LAWNS 10 DAYS AFTER REPLANTING.
- C. SEEDED AREA: TRENCHING WILL BE REQUIRED ACROSS EXISTING SEEDED AREAS, PRIMARILY ROADWAY EDGING. THE CONTRACTOR SHALL CONFORM TO THE REQUIREMENTS OF SEEDING, SECTION 02930 FOR THE RESEEDING OF THE DISTURBED TRENCH AREA.
- D. PAVEMENTS: JACK AND BORE OR DIRECTIONAL BORE PIPING UNDER PAVING MATERIALS AS PER LOCAL

REGULATORY CODES. NO CUTTING AND PATCHING OF PAVEMENT WILL BE PERMITTED.

- A. ISOLATION VALVES: SHALL BE SIZED CORRESPONDING TO ADJACENT PIPE SIZE. SPECIFIED VALVE BOXES SHALL BE INSTALLED FLUSH WITH FINISH GRADE IN SUCH A MANNER THAT SURFACE FORCES APPLIED TO THEIR EXPOSED AREA WILL NOT BE TRANSMITTED TO THE PIPING IN WHICH THE VALVE IS INSTALLED NOR ANY OTHER PIPING, WIRING OR OTHER LINES IN THE VICINITY OF SAID VALVES.
- B. GATE VALVES: INSTALL WHERE SHOWN, IN VALVE BOXES.
- C. ELECTRIC CONTROL VALVES: SHALL BE INSTALLED IN SPECIFIED VALVE BOXES. THE VALVE SHALL HAVE 6" OF 3/4" PEA GRAVEL INSTALLED BELOW THE BOTTOM OF THE VALVE. IF THE VALVE BOX DOES NOT EXTEND TO THE BASE OF THE VALVE, A VALVE BOX EXTENSION SHALL BE INSTALLED. ELECTRIC CONTROL VALVES SHALL BE INSTALLED WHERE SHOWN AND GROUPED TOGETHER WHERE PRACTICAL. THE CONTRACTOR SHALL PLACE NO CLOSER THAN 24" TO WALK EDGES, BIKEWAY EDGES, BUILDINGS AND WALLS. THE CONTRACTOR SHALL ADJUST THE VALVE TO PROVIDE FLOW RATE OR RATED OPERATING PRESSURE REQUIRED FOR EACH SPRINKLER

### 3.07 CONDUIT AND SLEEVES

- A. CONDUIT AND SLEEVES FOR CONTROL WIRING AND MAIN/LATERAL PIPE: THE CONTRACTOR SHALL PROVIDE AND INSTALL WHERE NECESSARY. CONTRACTOR SHALL COORDINATE LOCATIONS OF PREVIOUSLY INSTALLED SLEEVING WITH THE GENERAL SITE CONTRACTOR.
- 1. THE CONTRACTOR SHALL COORDINATE INSTALLATION OF SLEEVES WITH WORK OF OTHER DISCIPLINES.
- A. THE CONTRACTOR SHALL CONNECT ELECTRIC CONTROL VALVES TO CONTROLLERS IN A CLOCKWISE SEQUENCE TO CORRESPOND WITH STATION SETTINGS BEGINNING WITH STATIONS 1, 2, 3, ETC. AUTOMATIC CONTROLLERS SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR AS NOTED ON THE DRAWINGS. ALL
- ZONES WILL BE LABELED ON THE CONTROLLER. B. CONTROLLERS SHALL BE EQUIPPED WITH LIGHTNING PROTECTION AND GROUNDED TO A STANDARD 5/8"
- COPPER CLAD STEEL GROUND ROD DRIVEN A MINIMUM OF 8' INTO THE GROUND AND CLAMPED. C. THE ELECTRICAL SERVICE TO THE CONTROLLERS SHALL BE PERFORMED BY AN ELECTRICAL SUBCONTRACTOR IN COMPLIANCE WITH NEC REQUIREMENTS.

- A. CONTROL WIRING BETWEEN THE CONTROLLER AND ELECTRIC VALVES SHALL BE BURIED IN MAIN LINE TRENCHES OR IN SEPARATE TRENCHES. ELECTRICAL CONNECTION AT VALVE WILL ALLOW FOR PIGTAIL SO SOLENOID CAN BE REMOVED FROM VALVE WITH SUFFICIENT SLACK TO ALLOW ENDS TO BE PULLED 12" ABOVE GROUND FOR EXAMINATION AND CLEANING.
- B. AN EXPANSION LOOP SHALL BE PROVIDED AT EVERY VALVE AT 100' O.C. EXPANSION LOOP SHALL BE FORMED BY WRAPPING WIRE AT LEAST EIGHT TIMES AROUND A 3/4" PIPE AND WITHDRAWING PIPE
- C. THE WIRE SHALL BE BUNDLED AND TAPED EVERY TEN FEET. THE WIRE SHALL BE LAID IN THE TRENCH PRIOR TO INSTALLING THE PIPE BEING CAREFUL TO INSTALL WIRE BENEATH AND 6" TO THE SIDE OF THE MAIN PIPE LINE.

a. POWER CONNECTIONS: ELECTRICAL CONNECTIONS TO POWER AND SIGNAL WIRES SHALL BE

D. ELECTRICAL CONNECTIONS TO ELECTRIC CONTROL VALVES SHALL BE MADE WITH RAINBIRD PEN-TITE OR TECHDEL GT-3-GEL - TITE CONNECTORS OR EQUAL.

### MADE USING 3M 82-A2 POWER CABLE SPLICE KITS. 3.10 SPRINKLER HEADS

- 1. SPRINKLER HEADS SHALL BE INSTALLED AS DESIGNATED ON THE SHOP DRAWINGS. HEADS SHALL BE
- INSTALLED ON FLEXIBLE PVC. TOP TO BE FLUSH WITH FINISH GRADE OR TOP OF CURB. 2. SPACING OF HEADS SHALL NOT EXCEED THE MAXIMUM INDICATED ON THE SHOP DRAWINGS (UNLESS DIRECTED BY THE LANDSCAPE ARCHITECT). IN NO CASE SHALL THE SPACING EXCEED THE MAXIMUM
- RECOMMENDED BY THE MANUFACTURER.
- 1. POP-UP- ROTARY SPRINKLER HEADS: SHALL BE INSTALLED ON FLEX JOINT AND BE SET WITH TOP OF HEAD FLUSH WITH FINISH GRADE. HEADS INSTALLED AT CURB SHALL HAVE 6" TO 10" BETWEEN PERIMETER OF HEAD AND CONCRETE. HEADS PLACED AT EDGE OF PAVEMENT HAVING NO CURB SHALL BE INSTALLED 24"
- 2. SPRAY POP-UP SPRINKLER HEADS: SHALL BE INSTALLED ON FLEXIBLE PVC AND BE SET WITH TOP OF HEAD FLUSH WITH FINISHED GRADE. SPRINKLER HEADS PLACED ADJACENT TO CURBS WILL BE INSTALLED 9" FROM CONCRETE. SPRINKLER HEADS PLACED ADJACENT TO PAVEMENT HAVING NO CURB SHALL BE INSTALLED 24" FROM THE EDGE OF PAVEMENT.
- 3.11 COMPLETION
- A. FLUSHING: BEFORE SPRINKLER HEADS ARE SET, THE CONTRACTOR SHALL FLUSH THE LINES THOROUGHLY TO MAKE SURE THERE IS NO FOREIGN MATTER IN THE LINES.
- 1. THE CONTRACTOR SHALL FLUSH THE MAIN LINES FROM DEAD END FITTINGS FOR A MINIMUM OF FIVE MINUTES UNDER A FULL HEAD OF PRESSURE. B. TESTING: THE CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT AND OWNER FORTY-EIGHT (48) HOURS IN
- ADVANCE OF TESTING. 1. PRIOR TO BACKFILLING OF MAIN LINE FITTINGS, CONTRACTOR SHALL FILL THE MAIN LINE PIPING WITH WATER, IN THE PRESENCE OF THE OWNER/LANDSCAPE ARCHITECT, TAKING CARE TO PURGE THE AIR FROM IT BY OPERATING ALL THE SPRINKLER CONTROL VALVES ONE OR MORE TIMES AND/OR SUCH OTHER MEANS AS MAY BE NECESSARY. A SMALL, HIGH PRESSURE PUMP OR OTHER MEANS OF MAINTAINING A CONTINUOUS WATER SUPPLY SHALL BE CONNECTED TO THE MAIN LINE AND SET SO AS TO MAINTAIN 100 PSI IN THE MAIN LINE SYSTEM FOR TWO (2) HOURS WITHOUT INTERRUPTION. WHEN THIS HAS BEEN ACCOMPLISHED AND WHILE THE PRESSURE IN THE SYSTEM IS STILL 100 PSI, LEAKAGE TESTING SHALL BE PERFORMED IN ACCORDANCE WITH AWWA STANDARD C-600. PRESSURE READINGS SHALL BE NOTED AND MAKE UP WATER USAGE SHALL BE RECORDED. SHOULD THE RATE OF MAKE UP WATER USAGE INDICATE SIGNIFICANT LEAKAGE, THE SOURCE OF SUCH LEAKAGE SHALL BE FOUND AND CORRECTED AND THE SYSTEM THEN RETESTED UNTIL THE OWNER/LANDSCAPE ARCHITECT IS SATISFIED THAT THE SYSTEM IS REASONABLY SOUND. LATERAL LINE TESTING SHALL BE CONDUCTED DURING THE OPERATING TESTING OF THE SYSTEM BY CHECKING VISUALLY THE GROUND SURFACE UNTIL NO LEAKS IN THIS PORTION OF THE SYSTEM ARE EVIDENT.
- WARRANTY PERIOD. 2. ADJUSTMENT AND COVERAGE OF SYSTEM: COORDINATE PRESSURE TESTING WITH ADJUSTMENTS AND COVERAGE TEST OF SYSTEM SO BOTH MAY OCCUR AT THE SAME TIME. THE CONTRACTOR SHALL BALANCE AND ADJUST THE VARIOUS COMPONENTS OF THE SYSTEM SO THAT THE OVERALL OPERATION OF THE SYSTEM IS MOST EFFICIENT. THIS INCLUDES A SYNCHRONIZATION OF THE CONTROLLERS, ADJUSTMENTS TO PRESSURE REGULATORS, PRESSURE RELIEF VALVES, PART CIRCLE SPRINKLER HEADS, AND INDIVIDUAL

LEAKS SHALL BE REPAIRED OR PAID FOR BY THE CONTRACTOR AT ANY TIME THEY APPEAR DURING THE

## STATION ADJUSTMENTS ON THE CONTROLLERS.

- 3.12 WARRANTY A. THE CONTRACTOR SHALL FULLY WARRANT THE LANDSCAPE IRRIGATION SYSTEM FOR A PERIOD OF ONE (1) YEAR AFTER THE WRITTEN FINAL ACCEPTANCE AND WILL RECEIVE A WRITTEN CONFIRMATION FROM THE
- LANDSCAPE ARCHITECT THAT THE WARRANTY PERIOD IS IN EFFECT. B. DURING THE WARRANTY PERIOD, THE CONTRACTOR WILL ENFORCE ALL MANUFACTURER'S AND SUPPLIER'S WARRANTIES AS IF MADE BY THE CONTRACTOR HIMSELF. ANY MALFUNCTIONS, DEFICIENCIES, BREAKS, DAMAGES, DISREPAIR, OR OTHER DISORDER DUE TO MATERIALS, WORKMANSHIP, OR INSTALLATION BY THE CONTRACTOR AND HIS SUPPLIERS SHALL BE IMMEDIATELY AND PROPERLY CORRECTED TO THE PROPER ORDER AS DIRECTED BY THE OWNER AND/OR LANDSCAPE ARCHITECT.
- C. ANY DAMAGES CAUSED BY SYSTEM MALFUNCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR WHO SHALL MAKE FULL AND IMMEDIATE RESTORATION FOR SAID DAMAGES.

CITY OF PORT ST. LUCIE PROJECT PSLUSD PROJECT #

SHEET NUMBER

Ŋ

CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE.

ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF

Call before you dig.

1.02 QUALITY ASSURANCE SUBMITTAL TO OWNER FOR FINAL PAYMENTS, INCLUDING RETENTIONS. A. INSTALLER QUALIFICATIONS: A FIRM SPECIALIZING IN IRRIGATION WORK WITH NOT LESS THAN FIVE (5) YEARS OF EXPERIENCE IN INSTALLING IRRIGATION SYSTEMS SIMILAR TO THOSE REQUIRED FOR THIS PROJECT.

PLACEMENT OF UNDERGROUND MATERIALS WITH CONTRACTORS PREVIOUSLY WORKING UNDERGROUND IN

FOLLOWING ACTIONS AS REQUIRED WITH REGARD TO DAMAGE TO ANY OF THE OWNER'S PROPERTY. 1. ANY EXISTING BUILDING, EQUIPMENT, PIPING, PIPE COVERINGS, ELECTRICAL SYSTEMS, SEWERS, SIDEWALKS, DURING THE COURSE OF HIS WORK, WHETHER THROUGH NEGLIGENCE OR OTHERWISE, SHALL BE REPLACED

OF THE APPARATUS, EQUIPMENT OR APPLIANCE.

THE CONTRACTOR'S EXPENSE.

CUSTOMARILY ISSUED IN CONNECTION WITH THE CLASS OF WORK INVOLVED.

H. THE SUPERINTENDENT SHALL REPRESENT THE CONTRACTOR IN HIS ABSENCE AND ALL DIRECTIONS GIVEN TO

SATISFACTORY COMPLETION OF ALL WORK. ACCEPTANCE BY THE LANDSCAPE ARCHITECT AND/OR OWNER IN NO WAY REMOVES THE CONTRACTOR OF HIS RESPONSIBILITY TO MAKE FURTHER REPAIRS, CORRECTIONS AND

ALL DEFECTS IN MATERIAL, EQUIPMENT AND WORKMANSHIP TO THE SATISFACTION OF THE OWNER. REPAIRS, 1. THE GUARANTEE SHALL ALSO COVER REPAIR OF DAMAGE TO ANY PART OF THE PREMISES RESULTING FROM RESPONSIBLE FOR WORK DAMAGED BY OTHERS. REPAIRS, IF REQUIRED, SHALL BE DONE PROMPTLY. THE GUARANTEE SHALL STATE THE NAME OF THE OWNER, PROVIDE FULL GUARANTEE TERMS, EFFECTIVE AND

EMERGENCY WHERE. IN THE JUDGMENT OF THE OWNER, DELAY WOULD CAUSE SERIOUS LOSS OR DAMAGE

PROPOSED PLANTINGS, IN ACCORDANCE WITH THE SITE'S GOVERNING PERMITTING REQUIREMENTS AND AS M. ON-SITE OBSERVATION: AT ANY TIME DURING THE INSTALLATION OF THE IRRIGATION SYSTEM BY THE

1.03 SUBMITTALS

PROPOSES TO INSTALL B. COMMENCE NO WORK BEFORE APPROVAL OF MATERIAL LIST AND DESCRIPTIVE MATERIAL BY THE LANDSCAPE

CONTINUOUS WORKING PRESSURE OF 150P PSI. VALVE SHALL BE EQUIPPED WITH A SQUARE OPERATING NUT.

2.11 VALVE BOXES

B. FOR CONTROL VALVES 3/4" THROUGH 2", THE DRIP VALVE ASSEMBLIES, USE AMETEK #10-181-014 BOX WITH #10-181-015 LOCKING LID, OR SIZED AS NECESSARY TO EFFECTIVELY HOUSE THE EQUIPMENT

DRAWINGS. 2.12 IRRIGATION WIRING

"HOT" OR LEAD WIRES, AND COMMON WIRE TO BE 14 GAUGE, WHITE IN COLOR.

B. CONTRACTOR SHALL PERFORM AN OHM TEST ON GROUND TO ASSURE ADEQUATE PROTECTION AGAINST SURGES AND INDIRECT LIGHTNING STRIKES.

# 2.13 MISCELLANEOUS MATERIALS

## 2.14 AUTOMATIC CONTROL SYSTEM

- 1. AN INDEPENDENT STATION CONTROLLER: FURNISH A SOLID STATE CONTROLLER, AS SPECIFIED ON THE
- STATION IN ONE (1) MINUTE INCREMENTS.
- c. THE STAND-ALONE CONTROLLER SHALL HAVE TWO (2) POSSIBLE PROGRAMS.
- (WATER BUDGET) FOR ALL STATIONS SIMULTANEOUSLY, FROM TEN (10) TO TWO HUNDRED (200) PERCENT, IN TEN (10) PERCENT INCREMENTS.
- INPUT WIRES WILL ALSO INCORPORATE SURGE PROTECTION. ALPHANUMERIC DISPLAYS OF DESCRIPTIVE ENGLISH MENUS AND LEGEND IDENTIFIERS WITH CURSOR
- OPERATING 24 VAC SOLENOIDS

- CONTRACTOR SHALL COORDINATE WITH OTHER TRADES AND INSTALL TO ACCURATE LEVELS PRIOR TO PAVING
- PIPE AND WIRE DEPTH
- CONTROL WIRING SIDE OF MAIN LINE

# RESPONSIBILITY FOR THE CORRECT INSTALLATION.

- 3.05 BACKFILLING PROCEDURES LINES AND FINAL HEAD LOCATIONS.
  - TRENCHES AS REQUIRED. CONSISTING OF EARTH, LOAM, SAND, AND OTHER APPROVED MATERIALS, FREE OF ROCK AND DEBRIS OVER
  - ON SO AS TO SECURE THE POSITION OF THE PIPE AND WIRE.

**GENERAL NOTES:** 

1. A MINIMUM OF 5' HORIZONTAL AND 18" VERTICAL SEPARATION SHALL BE MAINTAINED FROM ALL EXISTING PSLUSD UTILITIES, INCLUDING WATER METERS AND SERVICES

988 (NAVD '88). SUBTRACT 1.47' FROM NGVD '29 ELEVATION TO GET THE NAVD '88 ELEVATIO'

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED ON THIS PROJECT.

5436

G

2 7